

# **TR-115**

## **VDSL2 Functionality Test Plan**

**Issue: 3**  
**Issue Date: January 2016**

**Notice**

The Broadband Forum is a non-profit corporation organized to create guidelines for broadband network system development and deployment. This Broadband Forum Technical Report has been approved by members of the Forum. This Broadband Forum Technical Report is not binding on the Broadband Forum, any of its members, or any developer or service provider. This Broadband Forum Technical Report is subject to change, but only with approval of members of the Forum. This Technical Report is copyrighted by the Broadband Forum, and all rights are reserved. Portions of this Technical Report may be copyrighted by Broadband Forum members.

THIS SPECIFICATION IS BEING OFFERED WITHOUT ANY WARRANTY WHATSOEVER, AND IN PARTICULAR, ANY WARRANTY OF NONINFRINGEMENT IS EXPRESSLY DISCLAIMED. ANY USE OF THIS SPECIFICATION SHALL BE MADE ENTIRELY AT THE IMPLEMENTER'S OWN RISK, AND NEITHER the Forum, NOR ANY OF ITS MEMBERS OR SUBMITTERS, SHALL HAVE ANY LIABILITY WHATSOEVER TO ANY IMPLEMENTER OR THIRD PARTY FOR ANY DAMAGES OF ANY NATURE WHATSOEVER, DIRECTLY OR INDIRECTLY, ARISING FROM THE USE OF THIS SPECIFICATION.

Broadband Forum Technical Reports may be copied, downloaded, stored on a server or otherwise re-distributed in their entirety only, and may not be modified without the advance written permission of the Broadband Forum.

The text of this notice must be included in all copies of this Broadband Forum Technical Report.

**Issue History**

<b>Issue Number</b>	<b>Approval Date</b>	<b>Publication Date</b>	<b>Issue Editor</b>	<b>Changes</b>
1	November 2009		Michael Hanrahan, Huawei	Original
2	July 2012		Michael Hanrahan, Huawei	Next revision
2 Amendment 1	28 May 2013	1 June 2013	Aleksandra Kozarev, Lantiq	Next revision
2 Corrigendum 1	3 March 2014	3 April 2014	Aleksandra Kozarev, Lantiq	Next revision
2 Corrigendum 2	16 June 2014	7 July 2014	Aleksandra Kozarev, Lantiq	Next revision
3	25 January 2016	2 May 2016	Aleksandra Kozarev, Intel	Next revision

Comments or questions about this Broadband Forum Technical Report should be directed to [help@broadband-forum.org](mailto:help@broadband-forum.org).

<b>Editor</b>	Aleksandra Kozarev	Intel
<b>Physical Layer Transmission Work Area</b>	Les Brown	Huawei Technologies
	Massimo Sorbara	Qualcomm Incorporated
<b>Project Stream Leaders</b>	Lincoln Lavoie	UNH-IOL
	Aleksandra Kozarev	Intel

**TABLE OF CONTENTS**

<b>EXECUTIVE SUMMARY .....</b>	<b>9</b>
<b>1 PURPOSE AND SCOPE.....</b>	<b>10</b>
1.1 PURPOSE .....	10
1.2 SCOPE .....	10
<b>2 REFERENCES AND TERMINOLOGY.....</b>	<b>11</b>
2.1 CONVENTIONS .....	11
2.2 REFERENCES .....	11
2.3 DEFINITIONS .....	12
2.4 ABBREVIATIONS .....	12
2.5 G.997.1 PARAMETERS .....	16
2.5.1 <i>Far-end INM performance monitoring parameters</i> .....	18
2.5.2 <i>INM configuration parameters (downstream, upstream)</i> .....	18
<b>3 TECHNICAL REPORT IMPACT .....</b>	<b>20</b>
3.1 ENERGY EFFICIENCY.....	20
3.2 IPV6.....	20
3.3 SECURITY.....	20
3.4 PRIVACY .....	20
<b>4 TEST STRUCTURE.....</b>	<b>21</b>
4.1 TEST CONFIGURATIONS .....	21
4.2 SYSTEM UNDER TEST SETTINGS .....	22
4.2.1 <i>Band Profiles</i> .....	22
4.2.2 <i>Line Settings</i> .....	24
4.2.3 <i>Profile Line Combinations</i> .....	33
4.3 TEST PLAN PASSING CRITERIA.....	34
4.4 TEST SETUP.....	35
4.5 EQUIPMENT FEATURE TABLES .....	35
4.6 EQUATIONS FOR ESTIMATING BER.....	36
<b>5 PHYSICAL LAYER TESTS .....</b>	<b>37</b>
5.1 INTERLEAVING DELAY TEST .....	37
5.2 IMPULSE NOISE PROTECTION TEST .....	38
5.3 DUAL LATENCY TEST (OPTIONAL) .....	38
5.4 ON-LINE RECONFIGURATION TESTS .....	39
5.4.1 <i>Bitswap Test</i> .....	39
5.4.2 <i>Bitswap Test with Retransmission enabled</i> .....	41
5.4.3 <i>Wideband Bitswap Test</i> .....	43
5.4.4 <i>Seamless Rate Adaptation Test (Optional)</i> .....	45
5.4.5 <i>SOS Test (Optional)</i> .....	58
5.4.6 <i>Bitswap to Zero-Bit-Loading Test</i> .....	62
5.5 LOOP DIAGNOSTIC MODE TEST .....	63
5.6 VTU-R INVENTORY TEST .....	66
5.7 PSD TESTS.....	67
5.7.1 <i>PSD Test</i> .....	67
5.7.2 <i>Aggregate Transmit Power Test</i> .....	68

5.7.3	<i>In-band Spectral Shaping Test</i> .....	70
5.7.4	<i>Downstream Power Back-off Test</i> .....	72
5.7.5	<i>Upstream Power Back-off Test</i> .....	73
5.8	LONGITUDINAL CONVERSION LOSS (LCL) TEST .....	75
5.9	VTU-R INM.....	76
5.9.1	<i>Expected Results for Test 1</i> .....	78
5.9.2	<i>Expected Results for Test 2</i> .....	78
5.9.3	<i>Expected Results for Test 3</i> .....	79
5.9.4	<i>Expected Results for Test 5, 7 and 9</i> .....	79
5.9.5	<i>Expected results for Test 4, 6, 8 and 10</i> .....	79
5.9.6	<i>Expected Results for Test 11</i> .....	80
5.9.7	<i>Expected Results for Test 12</i> .....	80
5.9.8	<i>PEIN Test Sequence Definition</i> .....	80
5.10	DYING GASP TEST .....	81
<b>6</b>	<b>SYSTEM LEVEL TESTS</b> .....	<b>82</b>
6.1	64/65-OCTET ENCAPSULATION FAR-END PTM-TC PERFORMANCE MONITORING TEST (OPTIONAL) .....	82
<b>7</b>	<b>TESTING G.997.1 CONFIGURATION PARAMETERS AND PERFORMANCE MONITORING COUNTERS</b> .....	<b>84</b>
7.1	CONFIGURATION PARAMETER MINSNRM.....	84
7.2	CONFIGURATION PARAMETER TARSNRM .....	84
7.3	CONFIGURATION PARAMETER PSDMASK.....	85
7.4	CONFIGURATION PARAMETER VDSL2-CARMASK .....	86
7.5	CONFIGURATION PARAMETER MAXNOMATP .....	86
7.6	PERFORMANCE MONITORING COUNTERS FOR CODE VIOLATIONS AND ERRORED SECONDS 87	
7.7	PERFORMANCE MONITORING COUNTER FOR SES .....	90
7.8	PERFORMANCE MONITORING COUNTER FOR UNAVAILABLE SECONDS (UAS) .....	91
7.9	PERFORMANCE MONITORING COUNTERS FOR FULL INITIALIZATION AND FAILED FULL INITIALIZATION .....	92
7.10	INHIBITION OF PERFORMANCE MONITORING COUNTERS .....	93
<b>ANNEX A</b>	<b>PEIN TEST SEQUENCES</b> .....	<b>96</b>
<b>APPENDIX I</b>	<b>ADDITIONAL INFORMATION ABOUT OAM PROTOCOL DATA UNIT (OAMPDU)</b> .....	<b>97</b>

**List of Figures**

Figure 1 - Generic Test Configuration.....	21
Figure 2 - Test Setup for Configurations Using Data Layer.....	21
Figure 3 - Test Configuration for PSD Measurement Tests .....	22
Figure 4 - Alternative Test Configuration for PSD Measurement Tests .....	22
Figure 5 - REIN Noise for the inhibition test of CV, ES, SES and LOSS counter .....	93

## List of Tables

Table 1 - Common Band Profiles .....	23
Table 2 - List of Common Line Settings for VDSL2 Functionality Tests.....	24
Table 3 - Common Line Settings for BA17a0_D&UPBO Band Profile.....	24
Table 4 - Common Line Settings for BB17a_D&UPBO Band Profile .....	25
Table 5 - Common Line Settings for BA30a_D&UPBO Band Profile .....	25
Table 6 - Common Line Settings for BB30a_D&UPBO Band Profile .....	26
Table 7 - Common Line Settings for BA17ade_D&UPBO Band Profile .....	27
Table 8 - UPBOA and UPBOB for band-profile AA8d .....	28
Table 9 - UPBOA and UPBOB for band-profile BA17a0_D&UPBO, BB17a_D&UPBO .....	28
Table 10 - UPBOA and UPBOB for band-profiles CG8d, CG12a, CG17a, CG30a.....	28
Table 11 - General Line Settings .....	30
Table 12 - Specific line settings for F and I-FEC tests .....	32
Table 13: Specific line settings for Retransmission enabled tests .....	32
Table 14 - Test profiles .....	33
Table 15 - VTU-O Feature Table.....	35
Table 16 - VTU-R Feature Table.....	35
Table 17 - Interleaving Delay Test .....	37
Table 18 - Capabilities of Impulse Noise Protection .....	38
Table 19 - Verification of the Function of Dual Latency (Optional).....	39
Table 20 - Bitswap Test .....	39
Table 21 – Bitswap Test with retransmission .....	41
Table 22 - Wideband Bit Swap Test Noise Definition .....	43
Table 23 - DS Wideband Bit Swapping Test.....	44
Table 24 - US Wideband Bit Swapping Test.....	45
Table 25 - SRA Configuration.....	46
Table 26 - SRA fast mode test - Downstream .....	46
Table 27 - SRA fast mode test - Upstream .....	48
Table 28 - SRA interleaved mode test with DCID – Downstream.....	49
Table 29 - SRA interleaved mode test with DCID – Upstream.....	50
Table 30 - SRA retransmission test – Downstream .....	52
Table 31 - SRA retransmission test – Upstream.....	53
Table 32 - SRA retransmission with interleaving test– Downstream.....	54
Table 33 - SRA retransmission with interleaving test– Upstream.....	56
Table 34 – SOS Test in the Downstream.....	59
Table 35 - SOS Test in the Upstream .....	60
Table 36 - Bitswap to zero bit loading test .....	62
Table 37 - Test on Loop Diagnostic Mode requested by VTU-O .....	63
Table 38 - Test on Loop Diagnostic Mode requested by VTU-R.....	65
Table 39 - VTU-R Inventory Information Test .....	66
Table 40 - PSD Test.....	67
Table 41 - Aggregate Transmit Power Test.....	69
Table 42 - List of some predefined RFI Notches (source: Europe/Germany, incl. international amateur radio bands).....	70
Table 43 - In-band Spectral Shaping / RFI Notch Configuration Test .....	71
Table 44 - Downstream Power Back-Off Test .....	72
Table 45 - Upstream Power Back-Off Test .....	74
Table 46 - Longitudinal Conversion Loss (LCL) Test .....	76
Table 47 - VTU-R INM Tests.....	76

Table 48 - VTU-R INM Capability .....	77
Table 49 – Dying Gasp Test .....	81
Table 50 - 64/65-Octet Encapsulation Far-End PTM-TC Performance Monitoring Test (Optional)	83
Table 51 - MINSNRM Control Test.....	84
Table 52 - TARSNRM Control Test.....	84
Table 53 - PSDMASK Control Test .....	85
Table 54 - VDSL2 CARMASK Control Test.....	86
Table 55 - MAXNOMATP Control Test.....	86
Table 56 - Code Violation and Errored Seconds Test in the Fast Mode .....	87
Table 57 - Code Violation and Errored Seconds Test in the Interleaved Mode .....	89
Table 58 - SES Counter Reporting Test .....	90
Table 59 - Unavailable Seconds (UAS) Reporting Test.....	91
Table 60 - Full Initialization Count and Failed Full Initialization Count Test .....	92
Table 61 - Test of inhibition and non-inhibition of CV, ES, SES, LOSS counters.....	94
Table 62 - Example Information OAMPDU after OAM discovery .....	97
Table 63 - Variable Request OAMPDU to retrieve TCCRCErrors Counter.....	98
Table 64 - Variable Response OAMPDU to retrieve TCCRCErrors Counter .....	98
Table 65 - Variable Request OAMPDU to retrieve TCCodingViolations Counter .....	98
Table 66 - Variable Response OAMPDU to retrieve TCCodingViolations counter.....	99



## Executive Summary

TR-115, as part of the Broadband Suite, provides a set of test methods to verify a significant subset of the transceiver functional requirements of VDSL2 modems implemented in accordance with ITU-T G.993.2 (Very high speed Digital Subscriber Line transceivers 2) as well as physical layer OAM configuration and performance monitoring parameters defined in ITU-T G.997.1. Its key value is in the verification of transceiver functionalities and management parameters such that network operators may deploy interoperable and successful VDSL2 services in their networks.

TR-115 accompanies TR-114 "*VDSL2 Performance Test Plan*" and TR-138 "*Accuracy Tests For Test Parameters*". TR-114 provides a set of region specific performance requirements and test methods for VDSL2 modems implemented in accordance with ITU-T G.993.2. TR-138 defines the tests for verification of the accuracy of the reported test (Physical Layer OAM configuration and performance monitoring) parameters defined in ITU-T G.993.2 and G.997.1.

Changes made from Issue 2 to Issue 3:

- (a) Integrated *Issue 2 Amendment 1*, *Issue 2 Corrigendum 1* and *Issue 2 Corrigendum 2*
- (b) The following sections are updated:
  - (1) Section 4.2 *System Under Test Settings*
  - (2) Section 4.5 *Equipmen Feauters Tables*
  - (3) Section 5.2 *Impulse Noise Protection Test*
  - (4) Section 5.4 *On-Line Reconfiguration Tests*
  - (5) Section 5.7 *PSD Tests*
  - (6) Section 5.9 *VTU-R INM*
  - (7) Section 7.7 *Performance Monitoring Counter for SES*
  - (8) Section 7.9 *Performance Monitoring Counters for Full initialization and Failed Full initialization*

## 1 Purpose and Scope

### 1.1 Purpose

This test plan describes a series of functionality tests that are used to verify that a VTU (VTU-O or VTU-R) is functionally compliant to ITU-T Recommendation G.993.2 (Very High Speed Subscriber Line transceiver 2). A VTU is functionally compliant to this test plan if it implements correctly the required functions and features of the ITU-T Recommendation G.993.2. In addition the VTU is functionally compliant if it implements the optional feature as specified in the standard. TR-115 also defines tests for some of the VDSL2 optional features such as dual latency and Seamless Rate Adaptation (SRA).

This functionality test plan does not specify the rate/reach performance requirements for VDSL2 transceiver. Instead, the reader is referred to TR-114 (VDSL2 performance test plan).

### 1.2 Scope

This test plan facilitates VDSL2 over POTS and over ISDN functional testing. This test plan embodies operators' definitions of VDSL2 interoperability (between one VTU-O and one VTU-R at a time). The test plan focuses on physical layer testing, and also validation and verification of selected higher layer functionality. It does not replace operators' pre-deployment testing.

This test plan defines tests for various physical layer functionalities and some higher layer functionalities. A pass/fail indication result is provided for each functionality test

NOTE - There is no requirement for VDSL2 VTUs to interoperate with G.993.1 (VDSL1) VTUs.

## 2 References and Terminology

### 2.1 Conventions

In this Technical Report, several words are used to signify the requirements of the specification. These words are always capitalized. More information can be found in RFC 2119 [15].

<b>SHALL</b>	This word, or the term “REQUIRED”, means that the definition is an absolute requirement of the specification.
<b>SHALL NOT</b>	This phrase means that the definition is an absolute prohibition of the specification.
<b>SHOULD</b>	This word, or the adjective “RECOMMENDED”, means that there could exist valid reasons in particular circumstances to ignore this item, but the full implications need to be understood and carefully weighed before choosing a different course.
<b>SHOULD NOT</b>	This phrase, or the phrase "NOT RECOMMENDED" means that there could exist valid reasons in particular circumstances when the particular behavior is acceptable or even useful, but the full implications need to be understood and the case carefully weighed before implementing any behavior described with this label.
<b>MAY</b>	This word, or the adjective “OPTIONAL”, means that this item is one of an allowed set of alternatives. An implementation that does not include this option SHALL be prepared to inter-operate with another implementation that does include the option.

### 2.2 References

The following references are of relevance to this Technical Report. At the time of publication, the editions indicated were valid. All references are subject to revision; users of this Technical Report are therefore encouraged to investigate the possibility of applying the most recent edition of the references listed below.

A list of currently valid Broadband Forum Technical Reports is published at [www.broadband-forum.org](http://www.broadband-forum.org).

Document	Title	Source	Year
[1] TR-100	<i>ADSL2/ADSL2plus Performance Test Plan</i>	BBF	2007
[2] TR-114 Issue 2	<i>VDSL2 Performance Test Plan</i>	BBF	2012
[3] G.117	<i>Transmission aspects of unbalance about earth</i>	ITU-T	1996
[4] G.992.3	<i>Asymmetric digital subscriber line transceivers 2 (ADSL2)</i>	ITU-T	2009
[5] G.992.5	<i>Asymmetric Digital Subscriber Line</i>	ITU-T	2009

		<i>(ADSL) transceivers - Extended bandwidth ADSL2 (ADSL2plus)</i>		
[6]	G.993.2	<i>Very high speed subscriber line transceivers 2 (VDSL2)</i>	ITU-T	2011
[7]	G.993.2 Amendment 5		ITU-T	2014
[8]	G.997.1	<i>Physical Layer Management for Digital Subscriber Line (DSL) Transceivers.</i>	ITU-T	2012
[9]	G.998.4	<i>Improved impulse noise protection for DSL transceivers, including all in force amendments and corrigenda</i>	ITU-T	2011
[10]	O.9	<i>Measuring arrangements to assess the degree of unbalance about earth</i>	ITU-T	1999
[11]	T1.417 Issue 2	<i>Spectrum Management for Loop Transmission System</i>	ANSI Standard	2003
[12]	802.3	<i>CSMA/CD access method and physical layer specifications</i>	IEEE	2005
[13]	802.3ah	<i>Ethernet in the First Mile</i>	IEEE	2005
[14]	RFC 1242	<i>Benchmarking terminology for network interconnection devices.</i>	IETF	1991
[15]	<a href="#">RFC 2119</a>	<i>Key words for use in RFCs to Indicate Requirement Levels</i>	IETF	1997
[16]	RFC 2544	<i>Benchmarking terminology for network interconnection devices (Test methodology).</i>	IETF	1999

## 2.3 Definitions

The following terminology is used throughout this Technical Report.

<b>All Digital Loop</b>	A digital subscriber line which is not shared by POTS or ISDN
<b>Ethernet Frame Size</b>	Size of the Ethernet frame including the CRC Checksum. See Section 3.5/RFC 1242.
<b>F<sub>max</sub></b>	The higher of the highest passband frequency in the upstream and downstream directions for the Limit PSD masks selected.
<b>L0</b>	State achieved after the initialization procedure has completed successfully
<b>L3</b>	State reached upon guided power removal, power loss or persistent link failures during Showtime
<b>Net Data Rate</b>	Sum of net data rates of all bearer channels
<b>Null Loop</b>	VTU-O/VTU-R wired “back to back” i.e. a zero length loop
<b>Showtime</b>	VTU-O and VTU-R trained up to the point of passing data.

## 2.4 Abbreviations

This Technical Report uses the following abbreviations:

<b>ANSI</b>	American National Standards Institute
<b>ATIS</b>	Alliance for Telecommunications Industry Solutions
<b>ATP</b>	Aggregate Transmit Power
<b>ATTNDR</b>	Attainable Net Data Rate
<b>AWG</b>	American Wire Gauge
<b>AWGN</b>	Additive White Gaussian Noise
<b>BER</b>	Bit error ratio
<b>BS</b>	Bitswap
<b>CRC</b>	Cyclic redundancy check
<b>CV</b>	Code Violations
<b>DCID</b>	Dynamic change of interleaving depth
<b>DPBO</b>	Downstream Power Back-Off
<b>DS</b>	Downstream
<b>EE</b>	Energy Efficiency
<b>ER(n)</b>	Expected Result step n
<b>ES</b>	Errored Seconds
<b>ETSI</b>	European Telecommunications Standards Institute
<b>EU</b>	Expanded Upstream
<b>FX</b>	Fixed Rate
<b>HI</b>	High Impulse Noise Protection
<b>HLING</b>	H(f) linear subcarrier group size
<b>HLINps</b>	H(f) linear representation
<b>HLINSC</b>	H(f) linear representation Scale
<b>HLOGG</b>	H(f) logarithmic subcarrier group size
<b>HLOGMT</b>	H(f) logarithmic Measurement Time
<b>HLOGps</b>	H(f) logarithmic representation
<b>IAT_REIN_RTX</b>	REIN inter-arrival time for retransmission
<b>ID</b>	Identification
<b>IEEE</b>	Institute of Electrical and Electronics Engineers
<b>INM</b>	Impulse Noise Monitoring
<b>INP</b>	Impulse Noise Protection
<b>INPMIN</b>	Minimum impulse noise protection
<b>INPMIN_REIN_RTX</b>	Minimum impulse noise protection against REIN for retransmission for a system using 4.3125 kHz subcarrier spacing
<b>INPMIN_SHINE_RTX</b>	Minimum impulse noise protection against SHINE for retransmission for a system using 4.3125 kHz subcarrier spacing
<b>INPMIN8</b>	Minimum impulse noise protection for system using 8.625 kHz subcarrier spacing
<b>INPMIN8_REIN_RTX</b>	Minimum impulse noise protection against REIN for retransmission for a system using 8.625 kHz subcarrier spacing
<b>INPMIN8_SHINE_RTX</b>	Minimum impulse noise protection against SHINE for retransmission for a system using 8.625 kHz subcarrier spacing
<b>ISDN</b>	Integrated Services Digital Network
<b>ITU</b>	International Telecommunication Union
<b>LATN</b>	Loop Attenuation
<b>LEFTR_THRESH</b>	Threshold for declaring a near-end "left" defect in retransmission operation
<b>LCL</b>	Longitudinal Conversion Loss
<b>LD</b>	Loop Diagnostic

<b>LDSF</b>	Loop Diagnostic Mode Forced
<b>LLC</b>	Link Layer Control
<b>LOS</b>	Loss-of-signal
<b>LPR</b>	Loss-of-power
<b>MAC</b>	Medium Access Control
<b>MAXNOMATP</b>	Maximum Nominal Aggregate Transmit Power
<b>MAXSNRM</b>	Maximum Signal to Noise Ratio Margin
<b>MIB</b>	Management Information Base
<b>MIN_NDR</b>	Minimum Net Data Rate
<b>MIN-SOS-BR</b>	Minimum SOS Bit Rate
<b>MINSNRM</b>	Minimum Signal to Noise Ratio Margin
<b>MOP(n)</b>	Method of Procedure step n
<b>NDR_REINIT</b>	Reinitialized Net Data Rate
<b>OAM</b>	Operations, Administration and Maintenance
<b>OLR</b>	Online reconfiguration
<b>PDU</b>	Protocol Data Unit
<b>PE</b>	Poly Ethylene (cable type)
<b>PMSF</b>	Power Management State Forced
<b>POTS</b>	Plain Old Telephone Service
<b>PSD</b>	Power Spectral Density
<b>PTM</b>	Packet Transfer Mode
<b>QLN</b>	Quiet Line Noise
<b>QLNG</b>	QLN(f) sub-carrier group size
<b>QLNMT</b>	Quiet Line Noise PSD Measurement Time
<b>QLNps</b>	Quiet Line Noise representation
<b>RA</b>	Rate Adaptive
<b>REIN</b>	Repetitive Electrical Impulse Noise
<b>RFC</b>	Request for Comments
<b>RFI</b>	Radio Frequency Interference
<b>ROC</b>	Robust Overhead Channel
<b>RTX_MODE</b>	Mode of operation of G.998.4 [9] retransmission
<b>SATN</b>	Signal Attenuation
<b>SES</b>	Severely Errored Second
<b>SHINERATIO_RTX</b>	SHINERATIO (loss of rate in a 1 second interval expressed as a fraction of NDR due to a SHINE impulse) in retransmission operation
<b>SNRG</b>	SNR(f) sub-carrier group size
<b>SNRM</b>	Signal to Noise Ratio Margin
<b>SNRMT</b>	SNR Measurement Time
<b>SNRps</b>	SNR(f) representation
<b>SRA</b>	Seamless Rate Adaptation
<b>SUT</b>	System Under Test
<b>TARSNRM</b>	Target Signal to Noise Ratio Margin
<b>TC(n)</b>	Test Configuration step n
<b>TR</b>	Technical Report
<b>UAS</b>	Un-Available Seconds
<b>UPBO</b>	Upstream Power Back-Off
<b>US</b>	Upstream
<b>VDSL2</b>	Very high speed digital subscriber line transceivers 2
<b>VN</b>	Virtual Noise

<b>VTU</b>	VDSL2 Transceiver Unit
<b>VTU-O</b>	VTU at the ONU (or central office, exchange, cabinet, etc. i.e. operator end of the loop)
<b>VTU-R</b>	VTU at the remote site (i.e. subscriber end of the loop)

## 2.5 G.997.1 Parameters

<b>Parameter</b>	<b>Section in G.997.1</b>
ACTATP	7.5.1.24/25
ACTINP	7.5.2.4
ACTNDR	7.5.2.8
ATTNDR	7.5.1.19/20
BITSpsds	7.5.1.29.1
BITSpsus	7.5.1.29.2
CRC-PFE	7.2.5.2.1
CV-C	7.2.2.1.1
CV-CFE	7.2.2.2.1
CV-PFE	7.2.5.2.2
DPBO	7.3.1.2.13
ES-L	7.2.1.1.2
ES-LFE	7.2.1.2.2
FORCEINP	7.3.2.5
HLING	7.5.1.26.2/8
HLINSC	7.5.1.26.1/7
HLINps	7.5.1.26.3/9
HLOGMT	7.5.1.26.4/10
HLOGG	7.5.1.26.5/11
HLOGps	7.5.1.26.6/12
INPMIN	7.3.2.3
INPMIN_REIN_RTX	7.3.2.16
INPMIN_SHINE_RTX	7.3.2.13
INPMIN8	7.3.2.4
INPMIN8_REIN_RTX	7.3.2.17
INPMIN8_SHINE_RTX	7.3.2.14
LATN	7.5.1.9/10
LDSF	7.3.1.1.8
LIMITMASK	7.3.1.2.16
LOSS-L	7.2.1.1.4
LOSS-LFE	7.2.1.2.4
LPR-FE	7.1.1.2.3



MAXNOMATPds	7.3.1.2.3
MAXNOMATPus	7.3.1.2.4
MAXSNRMds	7.3.1.3.3
MAXSNRMus	7.3.1.3.4
MAX-SOS-ds	7.3.1.10.7
MAX-SOS-us	7.3.1.10.8
MIBMASK	7.2.3
MINSNRMds	7.3.1.3.5
MINSNRMus	7.3.1.3.6
MIN-SOS-BR-ds	7.3.2.1.6
MIN-SOS-BR-us	7.3.2.1.7
MREFPSD	7.5.1.29.7/8
MSGMINds	7.3.1.5.2
MSGMINus	7.3.1.5.1
PMSF	7.3.1.1.3
PMode	7.3.1.1.4
PSDMASKds	7.3.1.2.9
PSDMASKus	7.3.1.2.12
QLNG	7.5.1.27.2/5
QLNMT	7.5.1.27.1/4
QLNps	7.5.1.27.3/6
RA-DSNRMds	7.3.1.4.7
RA-DSNRMus	7.3.1.4.8
RA-DTIMEds	7.3.1.4.9
RA-DTIMEus	7.3.1.4.10
RA-MODEds	7.3.1.4.1
RA-MODEus	7.3.1.4.2
RA-USNRMds	7.3.1.4.3
RA-USNRMus	7.3.1.4.4
RA-UTIMEds	7.3.1.4.5
RA-UTIMEus	7.3.1.4.6
SATN	7.5.1.11/12
SES-L	7.2.1.1.3
SES-LFE	7.2.1.2.3
SNRG	7.5.1.28.2/5

SNRMds	7.5.1.13
SNRMODEds	7.3.1.7.1
SNRMODEus	7.3.1.7.2
SNRMT	7.5.1.28.1/4
SNRMus	7.5.1.16
SNRps	7.5.1.28.3/6
SOS-CRC-ds	7.3.1.10.5
SOS-CRC-us	7.3.1.10.6
SOS-TIME-ds	7.3.1.10.1
SOS-TIME-us	7.3.1.10.2
SOS-NTONES-ds	7.3.1.10.3
SOS-NTONES-us	7.3.1.10.4
TARSNRMds	7.3.1.3.1
TARSNRMus	7.3.1.3.2
UAS-L	7.2.1.1.5
UAS-LFE	7.2.1.2.5
UPBO	7.3.1.2.14
VDSL2-CARMASK	7.3.1.2.8

### 2.5.1 Far-end INM performance monitoring parameters

Parameter	Section in G.997.1
INM INPEQ histogram 1..17 (INMINPEQ <sub>1..17</sub> -LFE)	7.2.1.5.1
INM total measurement (INMME-LFE)	7.2.1.5.2
INM IAT histogram 0..7 (INMIAT <sub>0..7</sub> -LFE)	7.2.1.5.3

### 2.5.2 INM configuration parameters (downstream, upstream)

Parameter	Section in G.997.1
INM Inter Arrival Time Offset (INMIATods, INMIATous)	7.3.1.9.1
INM Inter Arrival Time Step (INMIATSds, INMIATSus)	7.3.1.9.2
INM Cluster Continuation value (INMCCds, INMCCus)	7.3.1.9.3

INM Equivalent INP Mode  
(INM\_INPEQ\_MODEEds,  
INM\_INPEQ\_MODEEus) 7.3.1.9.4

### **3 Technical Report Impact**

#### **3.1 Energy Efficiency**

TR-115 has no impact on Energy Efficiency.

#### **3.2 IPv6**

TR-115 has no impact on IPv6.

#### **3.3 Security**

TR-115 has no impact on Security.

#### **3.4 Privacy**

Any issues regarding privacy are not affected by TR-115.


### 4 TEST STRUCTURE

This section contains all the specifications and information required for building the basic testing environment (e.g. test configurations, setup of the simulated network environment, main settings of the equipment under test) for VDSL2 test cases defined in this test plan. Different configurations and settings needed for specific test cases are defined in the related section.


#### 4.1 Test Configurations

For tests that do not require data layer Figure 1 SHALL be used.

For tests that do require data layer Figure 2 SHALL be used.




**Figure 1 - Generic Test Configuration**




**Figure 2 - Test Setup for Configurations Using Data Layer**

NOTE - The modem SHALL be set to a bridged configuration.



**Figure 3 - Test Configuration for PSD Measurement Tests**



**Figure 4 - Alternative Test Configuration for PSD Measurement Tests**

NOTE – Test setups MAY use real cable instead of a loop simulator.

## 4.2 System Under Test Settings

### 4.2.1 Band Profiles

Band Profiles are used to describe the VDSL2 profile under test. The structure of the abbreviation used throughout the document for Band Profiles is as follows.

The abbreviation begins with a letter designating the G.993.2 Annex to which the profile refers. The next letter refers to the US0 type of the profile, hence indicating profiles for

- AA: G.993.2 Annex A with US0 corresponding to Annex A of G.992.5 (VDSL2 over POTS).
- BA: G.993.2 Annex B with US0 corresponding to Annex A of G.992.5 (VDSL2 over POTS). Note that the same abbreviation is used for profile 17a where US0 is not available.
- BB: G.993.2 Annex B with US0 corresponding to Annex B of G.992.5 (VDSL2 over ISDN).
- CG: G.993.2 Annex C (VDSL2 over TCM-ISDN). Note that US0 is not available.

The next symbols are the numeric and letter description of the profile itself (8a, 8b, 8d, 12a, 17a, 17a0, 30a, etc.).

Any VTU-O/VTU-R combination claiming TR-115 interoperability for a specific profile SHALL comply with the testing requirements for that profile. Claiming interoperability for several distinct profiles SHALL comply with each of the distinct profile test requirements. Common Band Profiles are provided in Table 1.

**Table 1 - Common Band Profiles**

<b>Annex A</b>				
<b>VDSL2 Band - profile</b>	AA8d	AA8a	AA12a	AA17a
Profile	8d	8a	12a	17a
Annex	A	A	A	A
Limit PSD Mask (LIMITMASK)	Table A.1/G.993.2	Table A.1/G.993.2	Table A.1/G.993.2	Table A.1/G.993.2
US0 type	EU32 (see Table A.2/G.993.2)	EU32 (see Table A.2/G.993.2)	EU32 (see Table A.2/G.993.2)	EU32 (see Table A.2/G.993.2)
MAXNOMATPds	+14.5 dBm	+17.5 dBm	+14.5 dBm	+14.5 dBm
<b>Annex B</b>				
<b>VDSL2 Band-profile</b>	BA8b	BA17ade	BA17a0	BA30a
Profile	8b	17a	17a	30a
Annex	B	B	B	B
Limit PSD Mask (LIMITMASK) (short name)	998-M2x-A (B8-4)	998ADE17-M2x-A (B8-11)	998E17-M2x-A (B8-18)	998E30-M2x-NUS0 (B8-13)
US0 type	A	A	A	N/A
MAXNOMATPds	+20.5 dBm	+14.5 dBm	+14.5 dBm	+14.5 dBm
<b>Annex B</b>				
<b>VDSL2 Band-profile</b>	BB8b	BB12a	BB17a	BB30a
Profile	8b	12a	17a	30a
Annex	B	B	B	B
Limit PSD Mask (LIMITMASK) (short name)	998-M2x-B (B8-6)	998-M2x-B (B8-6)	998ADE17-M2x-B (B8-12)	998ADE30-M2x-NUS0-M (B8-15)
US0 type	B	B	B	N/A
MAXNOMATPds	+20.5 dBm	+14.5 dBm	+14.5 dBm	+14.5 dBm
<b>Annex C</b>				
<b>VDSL2 Band-profile</b>	CG8d	CG12a	CG17a	CG30a
Profile	8d	12a	17a	30a
Annex	C	C	C	C
Limit PSD Mask (LIMITMASK) (short name)	Tables C-9 and C-10/ G.993.2 (VDSL2 above TCM_ISDN band)	Tables C-9 and C-10/ G.993.2 (VDSL2 above TCM_ISDN band)	Tables C-9 and C-10/ G.993.2 (VDSL2 above TCM_ISDN band)	Tables C-9 and C-10/ G.993.2 (VDSL2 above TCM_ISDN band)
US0 type	N/A	N/A	N/A	N/A
MAXNOMATPds	+14.5dBm	+14.5dBm	+14.5dBm	+14.5dBm

## 4.2.2 Line Settings

### 4.2.2.1 Common Line Settings

This section defines the modem settings of parameters that are common to all of the configurations of the SUT in this test plan. Common line settings are provided in the following tables.

**Table 2 - List of Common Line Settings for VDSL2 Functionality Tests**

Parameter	Setting	Description
All parameters but those specified below	Default value	
Power management state forced (PMSF)	0	
Power management state enabling (PMMODE)	0	
Loop diagnostic mode forced (LDSF)	0	
Automode cold start forced	0	
DPBO	off	
UPBO	off	
RFI notches	off	
MAXSNRMds	FFFF <sub>16</sub>	
MAXSNRMus	FFFF <sub>16</sub>	
TARSNRMds	6 dB	
TARSNRMus	6 dB	
MINSNRMds	0 dB	
MINSNRMus	0 dB	
MSGMINds	16 kbps	
MSGMINus	16 kbps	
Preemption option flag, ds	00 <sub>16</sub>	PTM-TC options (Annex N/G.992.3 [4])
Preemption option flag, us	00 <sub>16</sub>	
Short packet option flag, ds	00 <sub>16</sub>	
Short packet option flag, us	00 <sub>16</sub>	
FORCEINP	1	
SNRMODEds	1	
SNRMODEus	1	

**Table 3 - Common Line Settings for BA17a0 D&UPBO Band Profile**

Parameter	Setting	Description
All parameters but those specified below	Value as specified in Table 2	
DPBOEPSD	ADSL2plus Annex A	PSD mask that is assumed to be permitted at the exchange
DPBOESEL	27dB@1MHz	E-side electrical length
DPBOESCMA	0.1924	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMA (NOTE)
DPBOESCMB	0.5960	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMB (NOTE)



DPBOESCMC	0.2086	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMC (NOTE)
DPBOMUS	-95 dBm/Hz	Minimum usable receive signal PSD mask
DPBOFMIN	138 kHz	Minimum frequency from which on the DPBO SHALL be applied
DPBOFMAX	2208 kHz	Maximum frequency up to which the DPBO SHALL be applied
UPBOKLF	0	Force CO-MIB electrical loop length (means that $kl_0$ is estimated during training)
UPBOKL	estimated during training	Upstream electrical loop length ( $kl_0$ )
NOTE - The values of DPBOESCMA, B and C are referred to a PE 0.4mm loop. Values that are configured according to G.997.1 SHALL be rounded to the nearest scalar value.		

**Table 4 - Common Line Settings for BB17a\_D&UPBO Band Profile**

Parameter	Setting	Description
All parameters but those specified below	Value as specified in Table 2	
DPBOEPSD	ADSL2plus Annex B	PSD mask that is assumed to be permitted at the exchange
DPBOESEL	27dB@1MHz	E-side electrical length
DPBOESCMA	0.1924	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMA (NOTE)
DPBOESCMB	0.5960	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMB (NOTE)
DPBOESCMC	0.2086	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMC (NOTE)
DPBOMUS	-95 dBm/Hz	Minimum usable receive signal PSD mask
DPBOFMIN	254 kHz	Minimum frequency from which on the DPBO SHALL be applied
DPBOFMAX	2208 kHz	Maximum frequency up to which the DPBO SHALL be applied
UPBOKLF	0	Force CO-MIB electrical loop length (means that $kl_0$ is estimated during training)
UPBOKL	estimated during training	Upstream electrical loop length ( $kl_0$ )
NOTE - The values of DPBOESCMA, B and C are referred to a PE 0.4mm loop. Values that are configured according to G.997.1 SHALL be rounded to the nearest scalar value.		

**Table 5 - Common Line Settings for BA30a\_D&UPBO Band Profile**

Parameter	Setting	Description
All parameters but those specified below	Value as specified in Table 2	
DPBOEPSD	ADSL2plus Annex A	PSD mask that is assumed to be permitted at the exchange
DPBOESEL	72dB@1MHz	E-side electrical length

DPBOESCMA	0.1924	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMA (NOTE)
DPBOESCMB	0.5960	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMB (NOTE)
DPBOESCMC	0.2086	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMC (NOTE)
DPBOMUS	-95 dBm/Hz	Minimum usable receive signal PSD mask
DPBOFMIN	138 kHz	Minimum frequency from which on the DPBO SHALL be applied
DPBOFMAX	2208 kHz	Maximum frequency up to which the DPBO SHALL be applied
UPBOKLF	0	Force CO-MIB electrical loop length (means that $kl_0$ is estimated during training)
UPBOKL	estimated during training	Upstream electrical loop length ( $kl_0$ )
UPBOA US0	40.00	A and B values US band 0 (these values imply no UPBO)
UPBOB US0	0	
UPBOA US1	47.30	A value US band 1
UPBOB US1	21.14	B value US band 1
UPBOA US2	54.00	A value US band 2
UPBOB US2	16.29	B value US band 2
UPBOA US3	54.00	A value US band 3
UPBOB US3	16.29	B value US band 3
UPBOA US4	40.00	A and B values US band 4 (these values imply no UPBO)
UPBOB US4	0	
NOTE - The values of DPBOESCMA, B and C are referred to a PE 0.4mm loop. Values that are configured according to G.997.1 SHALL be rounded to the nearest scalar value.		

**Table 6 - Common Line Settings for BB30a\_D&UPBO Band Profile**

Parameter	Setting	Description
All parameters but those specified below	Value as specified in Table 2	
DPBOEPSD	ADSL2plus Annex B	PSD mask that is assumed to be permitted at the exchange
DPBOESEL	72dB@1MHz	E-side electrical length
DPBOESCMA	0.1924	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMA (NOTE)
DPBOESCMB	0.5960	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMB (NOTE)
DPBOESCMC	0.2086	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMC (NOTE)

DPBOMUS	-95 dBm/Hz	Minimum usable receive signal PSD mask
DPBOFMIN	254 kHz	Minimum frequency from which on the DPBO SHALL be applied
DPBOFMAX	2208 kHz	Maximum frequency up to which the DPBO SHALL be applied
UPBOKLF	0	Force CO-MIB electrical loop length (means that $kl_0$ is estimated during training)
UPBOKL	estimated during training	Upstream electrical loop length ( $kl_0$ )
UPBOA US0	40.00	A and B values US band 0 (these values imply no UPBO)
UPBOB US0	0	
UPBOA US1	47.30	A value US band 1
UPBOB US1	21.14	B value US band 1
UPBOA US2	54.00	A value US band 2
UPBOB US2	16.29	B value US band 2
UPBOA US3	40.00	A and B values US band 3 (these values imply no UPBO)
UPBOB US3	0	
NOTE - The values of DPBOESCMA, B and C are referred to a PE 0.4mm loop. Values that are configured according to G.997.1 SHALL be rounded to the nearest scalar value.		

**Table 7 - Common Line Settings for BA17ade\_D&UPBO Band Profile**

Parameter	Setting	Description
All parameters but those specified below	Value as specified in Table 2	
DPBOEPSD	ADSL2plus Annex A	PSD mask that is assumed to be permitted at the exchange
DPBOESEL	27dB@1MHz	E-side electrical length
DPBOESCMA	0.1719	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMA (NOTE)
DPBOESCMB	0.644453	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMB (NOTE)
DPBOESCMC	0.18359	Model of the frequency dependent loss of E-side cable: scalars DPBOESCMC (NOTE)
DPBOMUS	-101.5 dBm/Hz	Minimum usable receive signal PSD mask
DPBOFMIN	138 kHz	Minimum frequency from which on the DPBO SHALL be applied
DPBOFMAX	2208 kHz	Maximum frequency up to which the DPBO SHALL be applied
UPBOKLF	0	Force CO-MIB electrical loop length (means that $kl_0$ is estimated during training)
UPBOKL	estimated during training	Upstream electrical loop length ( $kl_0$ )
UPBOA US0	40.00	A and B values US band 0 (these values imply no UPBO)
UPBOB US0	0	
UPBOA US1	60	A value US band 1

UPBOB US1	21	B value US band 1
UPBOA US2	60	A value US band 2
UPBOB US2	8	B value US band 2
NOTE - The values of DPBOESCMA, B and C are referred to a PE 0.4mm loop. Values that are configured according to G.997.1 SHALL be rounded to the nearest scalar value.		

**Table 8 - UPBOA and UPBOB for band-profile AA8d**

Parameter	Setting	Description
UPBOA US0	40.00	A and B values US band 0 (These values imply no UPBO)
UPBOB US0	0	
UPBOA US1	53	A value US band 1
UPBOB US1	21.2	B value US band 1
UPBOA US2	54	A value US band 2
UPBOB US2	18.7	B value US band 2

**Table 9 - UPBOA and UPBOB for band-profile BA17a0\_D&UPBO, BB17a\_D&UPBO**

Parameter	Setting	Description
UPBOA US0	40.00	A and B values US band 0 (These values imply no UPBO)
UPBOB US0	0	
UPBOA US1	47.30	A value US band 1
UPBOB US1	21.14	B value US band 1
UPBOA US2	54.00	A value US band 2
UPBOB US2	16.29	B value US band 2
UPBOA US3	54.00	A value US band 3
UPBOB US3	16.29	B value US band 3

NOTE - BB17a\_D&UPBO does not have US3.

**Table 10 - UPBOA and UPBOB for band-profiles CG8d, CG12a, CG17a, CG30a**

Parameter	Setting	Description
UPBOA US0	40	A and B values US band 0 (these values imply no UPBO)
UPBOB US0	0	
UPBOA US1	60	A value US band 1
UPBOB US1	10.2	B value US band 1
UPBOA US2	60	A value US band 2
UPBOB US2	6.42	B value US band 2
UPBOA US3	40	A value US band 3
UPBOB US3	0	B value US band 3

NOTE - CG8d does not have US2 and US3.

NOTE - CG12a does not have US3.

#### ***4.2.2.2 General Line Settings***

This section defines the profile, latency and impulse noise protection settings of the SUT. Deviations from these modem settings are indicated in the description of each test or test section.

General line settings are provided in Table 11.

**Table 11 - General Line Settings**

General line-setting	Parameter	Setting	Description
<b>F-1/0</b>	delay_max <sub>n</sub> ds	S1	Special value S1 as defined in section 7.3.2.2/ G.997.1 indicating that S and D SHALL be selected such that $S \leq 1$ and $D=1$
	delay_max <sub>n</sub> us	S1	Special value S1 as defined in section 7.3.2.2/ G.997.1 indicating that S and D SHALL be selected such that $S \leq 1$ and $D=1$
	INPMIN ds	0 symbols	
	INPMIN us	0 symbols	
<b>I-1/0</b>	delay_max <sub>n</sub> ds	S2	Special value S2 as defined in Section 7.3.2.2/ G.997.1 indicating a delay bound of 1 ms.
	delay_max <sub>n</sub> us	S2	Special value S2 as defined in Section 7.3.2.2/ G.997.1 indicating a delay bound of 1 ms.
	INPMIN ds	0 symbols	
	INPMIN us	0 symbols	
<b>I-8/2</b>	delay_max <sub>n</sub> ds	8 ms	
	delay_max <sub>n</sub> us	8 ms	
	INPMIN ds	2 symbols	
	INPMIN us	2 symbols	
<b>I-16/2</b>	delay_max <sub>n</sub> ds	16 ms	
	delay_max <sub>n</sub> us	16 ms	
	INPMIN ds	2 symbols	
	INPMIN us	2 symbols	
<b>I-32/16</b> <i>(Not applicable for 30 MHz profiles)</i>	delay_max <sub>n</sub> ds	32 ms	
	delay_max <sub>n</sub> us	32 ms	
	INPMIN ds	16 symbols	
	INPMIN us	16 symbols	
<b>R-17/2/41</b> <i>(applicable for retransmission enabled profiles)</i> (NOTE 2)	RTX_MODE	2	RTX_FORCED
	IAT_REIN_RTX	0	REIN at 100Hz
	INPMIN_REIN_RTX	2 symbols	DMT symbols protection against REIN
	INPMIN_SHINE_RTX	41 symbols	DMT symbols protection against PEIN/SHINE
	SHINERATIO_RTX	2	Worst case PEIN retransmission overhead (in %)
	LEFTR_THRESH	0.78	Low rate defect threshold
	DELAYMAX_RTX	17ms	

	DELAYMIN_RTX	0 ms	Outlet shaper off
<p>NOTE 1: For profiles up to 17MHz, INPMIN SHALL be set to INP_min. For 30MHz profiles, INPMIN8 SHALL be set to 2×INP_min.</p> <p>NOTE 2: For 30MHz profiles, INPMIN8_SHINE_RTX SHALL be set to 2xINPMIN_SHINE_RTX and INPMIN8_REIN_RTX SHALL be set to 2xINPMIN_REIN_RTX.</p>			

Note that these retransmission settings are defined for the specific purposes of this Test Plan, they do not necessarily represent a recommended configuration for the field.

#### 4.2.2.3 *Specific Line Settings*

The nomenclature adopted for the specific line settings is as follows:

- The first two letters describe whether the SUT operates in rate adaptive (RA) or fixed rate (FX) mode
- The next one or two letters describe the profile latency and INP settings according to Table 12 (Fast or Interleaved).
- The following two numbers are the upper limits of the downstream and upstream rates rounded and expressed in Mbps.

**Table 12 - Specific line settings for F and I-FEC tests**

<b>Specific line-setting</b>	<b>General line-setting</b>	<b>RA-Mode</b>	<b>DS net data rate (NDR) (kbit/s) (max- min)</b>	<b>US net data rate (NDR) (kbit/s) (max-min)</b>
RA_F_150_150	F-1/0	AT_INIT	150000-128	150000-64
RA_I_150_150	I-8/2	AT_INIT	150000-128	150000-64
FX_I_027_002	I-8/2	Manual	27000-27000	2000-2000
FX_I_014_001	I-8/2	Manual	14000-14000	1000-1000
FX_I_040_006	I-8/2	Manual	40400-40400	5700-5700
RA_I_096_056	I-8/2	AT_INIT	96000-256	56000-128
RA_I_105_105	I-1/0	AT_INIT	104960-64	104960-64
RA_HI_150_150	I-32/16	AT_INIT	150000-128	150000-64
RA_I_098_058	I-8/2	AT_INIT	98000-32	58000-32
RA_I_150_096	I-8/2	AT_INIT	150000-256	96000-128
FX_I_010_001	I-8/2	Manual	10000-10000	1000-1000
FX_I_050_020	I-8/2	Manual	50000-50000	20000-20000
FX_I_050_015	I-8/2	Manual	50000-50000	15000-15000
FX_I_075_025	I-8/2	Manual	75000-75000	25000-25000
FX_I_080_015	I-8/2	Manual	80000-80000	15000-15000
FX_I_047_019	I-8/2	Manual	47000-47000	19000-19000
FX_I_033_014	I-8/2	Manual	33000-33000	14000-14000
FX_I_018_005	I-8/2	Manual	18000-18000	5000-5000
FX_I_010_002	I-8/2	Manual	10000-10000	2000-2000
FX_HI_011_004	I-32/16	Manual	11000-11000	4000-4000
FX_HI_009_003	I-32/16	Manual	9000-9000	3000-3000

**Table 13: Specific line settings for Retransmission enabled tests**

<b>Specific line-setting</b>	<b>DS General line-setting</b>	<b>US General line-setting</b>	<b>RA-Mode</b>	<b>DS Expected throughput and net data rate (kbps) (ETR_RTX) (max-min) (NDR)(kbps) (max)</b>	<b>US Expected throughput and net data rate (kbps) (ETR_RTX) (max-min) (NDR)(kbps) (max)</b>
RA_R-17/2/41_150_150	R-17/2/41	R-17/2/41	AT_INIT	MAXETR_RTX= 150000 MAXNDR_RTX= 150000 MINETR_RTX= 518	MAXETR_RTX= 150000 MAXNDR_RTX= 150000 MINETR_RTX= 518



### 4.2.3 Profile Line Combinations

Common band-profiles as described in Section 4.2.1 are combined with line settings described in Section 4.2.2 to specify the common settings for a system under test. Without enumerating each combination a new nomenclature is formed using the concatenation of the two common setting nomenclatures. Table 14 provides a complete list of test profiles.

**Table 14 - Test profiles**

VDSL2 Band-profile	Specific line-setting	Profile-line combination
<b>Annex A</b>		
AA8a	RA_I_098_058	AA8a_UPBO_RA_I_098_058
AA12a	RA_I_098_058	AA12a_UPBO_RA_I_098_058
AA17a	RA_I_150_096	AA17a_UPBO_RA_I_150_096
AA17a	RA_R-17/2/41_150_096	AA17a_UPBO_RA_R-17/2/41_150_096
AA8d	RA_I_096_056	AA8d_UPBO_RA_I_096_056
AA8d	FX_I_027_002	AA8d_UPBO_FX_I_027_002
AA8d	FX_I_014_001	AA8d_UPBO_FX_I_014_001
AA8d	FX_I_040_006	AA8d_UPBO_FX_I_040_006
<b>Annex B</b>		
BA8b	RA_R_17/2/41_150_150	BA8b_RA_R-17/2/41_150_150
BA8b	RA_I_150_150	BA8b_RA_I_150_150
BA17a0	RA_R_17/2/41_150_150	BA17a0_RA_R-17/2/41_150_150
BA17a0	RA_I_150_150	BA17a0_RA_I_150_150
BA17a0_D&UPBO	RA_R_17/2/41_150_150	BA17a0_D&UPBO_RA_R-17/2/41_150_150
BA17a0_D&UPBO	RA_I_150_150	BA17a0_D&UPBO_RA_I_150_150
BA17a0_D&UPBO	FX_I_050_020	BA17a0_D&UPBO_FX_I_050_020
BA17ade_D&UPBO	RA_R-17/2/41_150_150	BA17ade_D&UPBO_RA_R-17/2/41_150_150
BA17ade_D&UPBO	RA_I_150_150	BA17ade_D&UPBO_RA_I_150_150
BA17ade_D&UPBO	FX_R-17/2/41_050_020	BA17ade_D&UPBO_FX_R-17/2/41_050_020
BA17ade_D&UPBO	FX_I_047_019	BA17ade_D&UPBO_FX_I_047_019
BA17ade_D&UPBO	FX_I_033_014	BA17ade_D&UPBO_FX_I_033_014
BA17ade_D&UPBO	FX_I_018_005	BA17ade_D&UPBO_FX_I_018_005
BA17ade_D&UPBO	FX_I_010_002	BA17ade_D&UPBO_FX_I_010_002

BA17ade_D&UPBO	RA_HI_150_150	BA17ade_D&UPBO_RA_HI_150_150
BA17ade_D&UPBO	FX_HI_011_004	BA17ade_D&UPBO_FX_HI_011_004
BA17ade_D&UPBO	FX_HI_009_003	BA17ade_D&UPBO_FX_HI_009_003
BA30a	RA_R_R- 17/2/41_150_150	BA30a_RA_R-17/2/41_150_150
BA30a	RA_I_150_150	BA30a_RA_I_150_150
BA30a_D&UPBO	RA_R_R- 17/2/41_150_150	BA30a_D&UPBO_RA_R-17/2/41_150_150
BA30a_D&UPBO	RA_I_150_150	BA30a_D&UPBO_RA_I_150_150
BA30a_D&UPBO	FX_I_075_025	BA30a_D&UPBO_FX_I_075_025
BB8b	RA_F_150_150	BB8b_RA_F_150_150
BB8b	RA_I_150_150	BB8b_RA_I_150_150
BB12a	RA_F_150_150	BB12a_RA_F_150_150
BB12a	RA_I_150_150	BB12a_RA_I_150_150
BB17a	RA_F_150_150	BB17a_RA_F_150_150
BB17a	RA_I_150_150	BB17a_RA_I_150_150
BB17a_D&UPBO	RA_F_150_150	BB17a_D&UPBO_RA_F_150_150
BB17a_D&UPBO	RA_I_150_150	BB17a_D&UPBO_RA_I_150_150
BB17a_D&UPBO	FX_I_050_015	BB17a_D&UPBO_FX_I_050_015
BB30a	RA_F_150_150	BB30a_RA_F_150_150
BB30a	RA_I_150_150	BB30a_RA_I_150_150
BB30a_D&UPBO	RA_F_150_150	BB30a_D&UPBO_RA_F_150_150
BB30a_D&UPBO	RA_I_150_150	BB30a_D&UPBO_RA_I_150_150
BB30a_D&UPBO	FX_I_080_015	BB30a_D&UPBO_FX_I_080_015
<b>Annex C</b>		
CG8d	RA_I_105_105	CG8d_RA_I_105_105
CG12a	RA_I_105_105	CG12a_RA_I_105_105
CG17a	RA_I_105_105	CG17a_RA_I_105_105
CG30a	RA_I_105_105	CG30a_RA_I_105_105

### 4.3 Test Plan Passing Criteria

For an SUT to pass this Test Plan for one of the VDSL2 band-profiles defined in Table 1, it is required that the SUT passes the mandatory test cases applicable to that band-profile and supported type of the TPS-TC layer.

#### 4.4 Test Setup

Loop models are specified in Section 6.3.2/TR-114 [2].

The following noise models are also specified in TR-114:

- Section 6.3.3.1/TR-114 for Region A VDSL2 profiles
- Section 6.3.3.2/TR-114 for Region B VDSL2 profiles
- Section 6.3.3.3/TR-114 for Region C VDSL2 profiles

Information on noise injection is specified in Section 6.3.4/TR-114.

#### 4.5 Equipment Feature Tables

The listed tables SHALL be filled with the requested information before starting the tests in order to have all the information about the system under test and to have a reproducible test environment.

**Table 15 - VTU-O Feature Table**

<b>Feature</b>	<b>Specification</b>
System Vendor ID	
G.994.1 Vendor ID	
Version Number	
Serial Number	
VDSL2 Band-Profiles supported: <ul style="list-style-type: none"> <li>- AA8d, AA8a, AA12a, AA17a</li> <li>- BA8b, BA17a0, BA17ade, BA30a</li> <li>- BB8b, BB12a, BB17a, BB30a</li> <li>- CG8d, CG12a, CG17a, CG30a</li> </ul>	
VDSL2 Band-Profiles tested	
VDSL2 optional features supported: <ul style="list-style-type: none"> <li>- Dual Latency</li> <li>- Seamless Rate Adaptation</li> <li>- SOS</li> <li>- Virtual Noise</li> </ul>	
VDSL2 optional features tested	
TPS-TC encapsulation supported: <ul style="list-style-type: none"> <li>- ATM</li> <li>- PTM</li> </ul>	
TPS-TC encapsulation tested (ATM, PTM)	

**Table 16 - VTU-R Feature Table**

<b>Feature</b>	<b>Specification</b>
System Vendor ID	
G.994.1 Vendor ID	
Version Number	
Serial Number	

VDSL2 Band-Profiles supported: <ul style="list-style-type: none"> <li>- AA8d, AA8a, AA12a, AA17a</li> <li>- BA8b, BA17a0, BA17ade, BA30a</li> <li>- BB8b, BB12a, BB17a, BB30a</li> <li>- CG8d, CG12a, CG17a, CG30a</li> </ul>	
VDSL2 Band-Profiles tested	
VDSL2 optional features supported: <ul style="list-style-type: none"> <li>- Dual Latency</li> <li>- Seamless Rate Adaptation</li> <li>- SOS</li> <li>- Virtual Noise</li> <li>- INM</li> </ul>	
VDSL2 optional features tested	
TPS-TC encapsulation supported: <ul style="list-style-type: none"> <li>- ATM</li> <li>- PTM</li> </ul>	
TPS-TC encapsulation tested (ATM, PTM)	

#### 4.6 Equations for Estimating BER

See Table 23/TR-114 [2] - *The equations for estimating BER.*

## 5 Physical Layer Tests

### 5.1 Interleaving Delay Test

The purpose of this test is to verify the validity of Interleaving Delay. It assumes that the system delay without interleaving delay is constant within a tolerance of 1ms and that the reported interleaving delay is equal to the actual delay.

**Table 17 - Interleaving Delay Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration depending on the customer interface of the modem.</li> <li>(2) According to the band-profile to be tested, configure the SUT with one of the profile line combinations using the general line setting I-8/2 associated to that band profile (see section 4.2.3). If for the specific band-profile, profile line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(3) Set loop for Null Loop without noise.</li> <li>(4) Setup the traffic generator/analyzer to send frames in one direction with destination MAC address equal to the unicast source MAC address of frames sent in the opposite direction.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Force a new initialization and wait for modems to sync.</li> <li>(2) Wait 1 minute after reaching Showtime.</li> <li>(3) Record Actual Interleaving Delay for both upstream and downstream as reported_delay_1_US and reported_delay_1_DS.</li> <li>(4) Run Section 26/RFC 2544 with a frame size of 512 bytes. Set the throughput rate to 90% of the achieved net data rate.</li> <li>(5) Record the result as system_delay_1_US and system_delay_1_DS.</li> <li>(6) Define “delta_delay_1” as the system delay without the interleaving delay in downstream and upstream:  <math display="block">\text{delta\_delay\_1\_DS} = \text{system\_delay\_1\_DS} - \text{reported\_delay\_1\_DS}</math> <math display="block">\text{delta\_delay\_1\_US} = \text{system\_delay\_1\_US} - \text{reported\_delay\_1\_US}</math> </li> <li>(7) Configure the SUT to the profile-line combination using the general line setting I-16/2, which otherwise is the same as the profile line combination of TC(2). If, for the specific band-profile, profile line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(8) Force a new initialization and wait for modems to sync.</li> <li>(9) Wait 1 minute after reaching Showtime.</li> <li>(10) Record Actual Interleaving Delay for both upstream and downstream as reported_Delay_2_US and reported_Delay_2_DS.</li> <li>(11) Run system delay test according to RFC 2544, with a frame size of 512. Set the throughput rate to 90% of the achieved net data rate.</li> <li>(12) Record the result as system_delay_2_US and system_delay_2_DS.</li> <li>(13) Define “delta_delay_2” as the system delay without the interleaving delay in downstream and upstream:  <math display="block">\text{delta\_delay\_2\_DS} = \text{system\_delay\_2\_DS} - \text{reported\_delay\_2\_DS}</math> <math display="block">\text{delta\_delay\_2\_US} = \text{system\_delay\_2\_US} - \text{reported\_delay\_2\_US}</math> </li> </ol>

<b>Expected Result</b>	The test is passed if the following conditions are met: (1) $\text{reported\_delay\_1\_US} \leq 8 \text{ ms}$ and $\text{reported\_delay\_1\_DS} \leq 8 \text{ ms}$ . (2) $\text{reported\_delay\_2\_US} \leq 16 \text{ ms}$ and $\text{reported\_delay\_2\_DS} \leq 16 \text{ ms}$ . (3) $ \text{delta\_delay\_1\_US} - \text{delta\_delay\_2\_US}  \leq 1 \text{ ms}$ . (4) $ \text{delta\_delay\_1\_DS} - \text{delta\_delay\_2\_DS}  \leq 1 \text{ ms}$ .
------------------------	---

## 5.2 Impulse Noise Protection Test

**Table 18 - Capabilities of Impulse Noise Protection**

<b>Test Configuration</b>	(1) See Section 4.1 for the test configuration depending on the customer interface of the modem. (2) According to the band-profile to be tested, configure the SUT with one of the profile line combinations using the general line setting I-8/2, I-16/2 or R-17/2/41 associated to that band profile (see section 4.2.3). If for the specific band-profile, profile-line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied. (3) Connect VTU-O and VTU-R to: <ul style="list-style-type: none"> <li>a. 2700 ft 26AWG for profiles up to 17MHz or 900 ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 900 m PE 0.4mm for profiles up to 17MHz or 300 m PE 0.4mm for 30MHz profiles</li> </ul>
<b>Method of Procedure</b>	(1) Inject white noise of -140dBm/Hz at the VTU-R end of the loop and -110 dBm/Hz at the VTU-O end of the loop. (2) Force initialization and wait for the modems to sync. (3) Wait for 1 minute after initialization. (4) Inject 15 impulses spaced at least 1 second apart into the circuit at the VTU-O end of the loop over a maximum of a one minute period. Each impulse SHALL be a “burst of pseudorandom AWGN” of 200us duration at a level of -90dBm/Hz differential mode. (5) Test the VTU-R modem by repeating the steps above, injecting the -140dBm/Hz white noise at the VTU-O end of the loop and -110dBm/Hz white noise and impulses at the VTU-R end of the loop.
<b>Expected Result</b>	(1) The number of errored seconds measured after the initial wait period SHALL be $\leq 1$ for the test to pass.

## 5.3 Dual Latency Test (Optional)

**Table 19 - Verification of the Function of Dual Latency (Optional)**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile-line combinations, except the ones with the retransmission general line setting, associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(3) Connect the VTU-R to the VTU-O through a loop with Noise generator, and connect VTU-R and VTU-O to Traffic Analyzer.</li> <li>(4) Set two channels with the following channel profiles F-1/0 for channel_1 and I-8/2 for channel_2.</li> <li>(5) Set up the loop to: <ol style="list-style-type: none"> <li>a. 2400 ft 26AWG for profiles up to 17MHz or 800 ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 750 m PE 0.4mm for profiles up to 17MHz or 250m PE 0.4mm for 30MHz profiles</li> </ol> </li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Inject white noise of -140dBm/Hz at the VTU-R end of the loop and -110dBm/Hz at the VTU-O end of the loop.</li> <li>(2) Train the modems using test profiles.</li> <li>(3) Wait for 1 minute after initialization.</li> <li>(4) Run Section 26.2/RFC2544 delay test using traffic analyzer in both channels, use Ethernet frame size of 1518 bytes. Record the result; Delay1 for channel_1 and Delay2 for channel_2.</li> <li>(5) Inject 15 impulses of 200us duration, a level of -90dBm/Hz differential mode and interval of 1 second at VTU-O end of the loop. Each impulse SHALL be a “burst of pseudorandom AWGN”.</li> <li>(6) Record the number of errored seconds reported.</li> <li>(7) Test the VTU-R modem by repeating the steps above, injecting the -140dBm/Hz white noise at the VTU-O end of the loop and -110dBm/Hz white noise and impulses at the VTU-R end of the loop.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) The measured delay on the low latency channel (Delay1) SHALL be &lt; the one of the higher latency (Delay2).</li> <li>(2) The number of reported code violations in channel_2 SHALL be &lt; channel_1.</li> </ol>

## 5.4 On-Line Reconfiguration Tests

### 5.4.1 Bitswap Test

The purpose of this test is to verify that the VTU-O and VTU-R support bit swapping per the Type 1 OLR on-line reconfiguration operation as defined in Section 13/G.993.2 [6].

**Table 20 - Bitswap Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) Connect VTU-O and VTU-R to: <ol style="list-style-type: none"> <li>a. 1350 ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450 m PE 0.4mm for profiles up to 17MHz or 150 m PE 0.4mm</li> </ol> </li> </ol>
---------------------------	---

	<p>for 30MHz profiles</p> <p>(3) According to the band-profile to be tested, configure the SUT with one of the profile line combinations, except the ones with the retransmission line setting, associated to that band-profile (see section 4.2.3). If for the specific band-profile, profile-line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(4) All single frequency tone amplitudes that are applied are referenced in terms of power levels (dBm) at the injection point on the loop, calibrated with the VTU-R and VTU-O modems replaced with calibrated 100 Ohm ±1% resistors. Measurements SHALL be performed into a 1kHz resolution bandwidth. Note that with a 1kHz resolution bandwidth the power spectral density value (in dBm/Hz) will be 30dB less than the power level (in dBm), limited by the noise floor of the test equipment used for calibration.</p> <p>(5) Set the noise generator to -140 dBm/Hz AWGN noise at both VTU-O and VTU-R.</p>
<p><b>Method of Procedure</b></p>	<p>(1) Force initialization and wait for the modems to sync.</p> <p>(2) Wait for 1 minute after initialization.</p> <p>(3) Record the bit allocation tables BITSpsus and BITSpsds.</p> <p>(4) Randomly select an integer value, n, the tone number in the range of one of the bands (DS or US) applicable to the chosen band-profile. Avoid the use of the pilot tone or any unpopulated tones. Ensure that the tone selected has assigned bits as described in the relevant bits per tone map, also after the injection of the RFI in MOP(5). The frequency of the interfering tone SHALL be set to n x 4.3125 kHz for profiles up to 17MHz or n x 8.625 kHz for 30MHz profiles.</p> <p>(5) The interfering tone SHALL be applied at the VTU-R side in the downstream bit swap test and at the VTU-O side in the upstream bit swap test. Its power SHALL be -110 dBm or less. Wait 60 seconds.</p> <p>(6) Record and report the value of n used.</p> <p>(7) Record BITSpsus and BITSpsds, and document them as BITSpsus_Old and BITSpsds_Old respectively.</p> <p>(8) Calculate and record the Transmitted_Bits_US_Old:</p> $\sum_i BITSpsus_i - \left\lceil \frac{NCUSEDus - \frac{NCONEBITus}{2}}{2} \right\rceil - 4$ <p>and the Transmitted_Bits_DS_Old:</p> $\sum_i BITSpsds_i - \left\lceil \frac{NCUSEDds - \frac{NCONEBITds}{2}}{2} \right\rceil - 4$ <p>where the <math>\lceil x \rceil</math> notation represents rounding to the next higher integer, the index ‘i’ denotes the carrier number, NCUSED represents the number of loaded sub-carriers and NCONEBIT is the number of sub-</p>



	<p>carriers with 1 bit.                  Transmitted_Bits_US_Old and Transmitted_Bits_DS_Old refer to the information bits from the PMS-TC. (See Figure 9-1/G.993.2).</p> <p>(9) Increase the power of the interfering tone to -50 dBm.</p> <p>(10) 2 minutes after increasing the tone power, record BITSpsus and BITSpsds, and document them as BITSpsus_New and BITSpsds_New respectively.</p> <p>(11) Calculate and record values of Transmitted_Bits_US_New and Transmitted_Bits_DS_New by using the formulas in (8).                  Transmitted_Bits_US_New and Transmitted_Bits_DS_New refer to the information bits from the PMS-TC. (See Figure 9-1/G.993.2).</p> <p>(12) Execute a BER test for 2 minutes.</p> <p>(13) Record the CRC and SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts.</p> <p>(14) Record the estimated BER (see Section 4.6)</p> <p>(15) Repeat MOP(1) to MOP(14) for each band applicable to the chosen band-profile.</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur during the test.</p> <p>(2) BITSpsus_New, recorded in step MOP(10), SHALL differ from BITSpsus_Old in step MOP(7), if tone n is in the bands of upstream direction.</p> <p>(3) BITSpsds_New, recorded in step MOP(10), SHALL differ from BITSpsds_Old in step MOP(7), if tone n is in the bands of downstream direction.</p> <p>(4) Transmitted_Bits_US_Old SHALL equal Transmitted_Bits_US_New.</p> <p>(5) Transmitted_Bits_DS_Old SHALL equal Transmitted_Bits_DS_New.</p> <p>(6) SES (as recorded in step MOP(13)) SHALL NOT increase.</p> <p>(7) The estimated BER SHALL NOT exceed <math>1e^{-7}</math>.</p>

**5.4.2 Bitswap Test with Retransmission enabled**

The purpose of this test is to verify that the VTU-O and VTU-R support bit swapping per the Type 1 OLR on-line reconfiguration operation as defined in Section 13/G.993.2 [6].

**Table 21 – Bitswap Test with retransmission**

<p><b>Test Configuration</b></p>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) Connect VTU-O and VTU-R to:</p> <ul style="list-style-type: none"> <li>a. 1350 ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450 m PE 0.4mm for profiles up to 17MHz or 150 m PE 0.4mm for 30MHz profiles</li> </ul> <p>(3) According to the band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3). If for the specific band-profile, profile-line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied. The test SHALL be done for the retransmission line setting (see section</p>
----------------------------------	---

	<p>4.2.2.2).</p> <p>(4) All single frequency tone amplitudes that are applied are referenced in terms of power levels (dBm) at the injection point on the loop, calibrated with the VTU-R and VTU-O modems replaced with calibrated 100 Ohm ±1% resistors. Measurements SHALL be performed into a 1kHz resolution bandwidth. Note that with a 1kHz resolution bandwidth the power spectral density value (in dBm/Hz) will be 30dB less than the power level (in dBm), limited by the noise floor of the test equipment used for calibration.</p> <p>(5) Set the noise generator to -140 dBm/Hz AWGN noise at both VTU-O and VTU-R.</p> <p>(6) SRA SHALL be disabled.</p>
<p><b>Method of Procedure</b></p>	<p>(1) Force initialization and wait for the modems to sync.</p> <p>(2) Wait for 1 minute after initialization.</p> <p>(3) Record the bit allocation tables BITSpsus and BITSpsds.</p> <p>(4) Randomly select an integer value, n, the tone number in the range of one of the bands (DS or US) applicable to the chosen band-profile. Avoid the use of the pilot tone or any unpopulated tones. Ensure that the tone selected has assigned bits as described in the relevant bits per tone map, also after the injection of the RFI in MOP(5). The frequency of the interfering tone SHALL be set to n x 4.3125 kHz for profiles up to 17MHz or n x 8.625 kHz for 30MHz profiles.</p> <p>(5) The interfering tone SHALL be applied at the VTU-R side in the downstream bit swap test and at the VTU-O side in the upstream bit swap test. Its power SHALL be -110 dBm or less. Wait 60 seconds.</p> <p>(6) Record and report the value of n used.</p> <p>(7) Record BITSpsus and BITSpsds, and document them as BITSpsus_Old and BITSpsds_Old respectively.</p> <p>(8) Calculate and record the Transmitted_Bits_US_Old:</p> $\sum_i BITSpsus_i - \left\lceil \frac{NCUSED_{us} - \frac{NCONEBIT_{us}}{2}}{2} \right\rceil - 4$ <p>and the Transmitted_Bits_DS_Old:</p> $\sum_i BITSpsds_i - \left\lceil \frac{NCUSED_{ds} - \frac{NCONEBIT_{ds}}{2}}{2} \right\rceil - 4$ <p>where the <math>\lceil x \rceil</math> notation represents rounding to the next higher integer, the index 'i' denotes the carrier number, NCUSED represents the number of loaded sub-carriers and NCONEBIT is the number of sub-carriers with 1 bit.</p> <p>Transmitted_Bits_US_Old and Transmitted_Bits_DS_Old refer to the information bits from the PMS-TC. (See Figure 9-1/G.993.2).</p> <p>(9) Increase the power of the interfering tone to -50 dBm.</p> <p>(10) 2 minutes after increasing the tone power, record BITSpsus and</p>

	<p>BITSpds, and document them as BITSpdsus_New and BITSpds_New respectively.</p> <p>(11) Calculate and record values of Transmitted_Bits_US_New and Transmitted_Bits_DS_New by using the formulas in (8). Transmitted_Bits_US_New and Transmitted_Bits_DS_New refer to the information bits from the PMS-TC. (See Figure 9-1/G.993.2).</p> <p>(12) Execute an CV, ES and SES counter test for 2 minutes.</p> <p>(13) Record the CV, ES and SES counts at the start and the end of the counter test. Actual number of CVs, ESs and SESs is the difference between these two counts.</p> <p>(14) Repeat MOP(1) to MOP(13) for each band applicable to the chosen band-profile.</p>
<b>Expected Result</b>	<p>(1) No retrain SHALL occur during the test.</p> <p>(2) BITSpdsus_New, recorded in step MOP(10), SHALL differ from BITSpdsus_Old in step MOP(7), if tone n is in the bands of upstream direction.</p> <p>(3) BITSpds_New, recorded in step MOP(10), SHALL differ from BITSpds_Old in step MOP(7), if tone n is in the bands of downstream direction.</p> <p>(4) Transmitted_Bits_US_Old SHALL equal Transmitted_Bits_US_New.</p> <p>(5) Transmitted_Bits_DS_Old SHALL equal Transmitted_Bits_DS_New.</p> <p>(6) No SES (as recorded in step MOP(13)) SHALL be reported.</p> <p>(7) No ES (as recorded in step MOP(13)) SHALL be reported.</p> <p>(8) No CV (as recorded in step MOP(13)) SHALL be reported.</p>

### 5.4.3 Wideband Bitwap Test

The purpose of this test is to verify that the VTU-O and VTU-R correctly perform bit swapping per Type 1 of OLR on-line reconfiguration operation when applying a wideband noise.

The noise defined in Table 22 forces the bit swapping between bands DS1 and DS2, and bands US1 and US2 of a 998 band plan.

The noise to be used for the wideband bitwap test is defined in Table 22.

The test procedure for the DS wideband bitwap test is defined in Table 23.

The test procedure for the US wideband bitwap test is defined in Table 24.

**Table 22 - Wideband Bit Swap Test Noise Definition**

f in kHz	Noise B-AWGN dBm/Hz	Noise B-DS1a dBm/Hz	Noise B-DS1b dBm/Hz	Noise B-DS2 dBm/Hz	Noise B-US1a dBm/Hz	Noise B-US1b dBm/Hz	Noise B-US2 dBm/Hz
25-2500	-110	-110	-110	-110	-110	-110	-110
2500-3650	-110	-104	-98	-110	-110	-110	-110
3650-3850	-110	-110	-110	-110	-110	-110	-110
3850-5100	-110	-110	-110	-110	-104	-98	-110
5100-5300	-110	-110	-110	-110	-110	-110	-110
5300-8400	-110	-110	-110	-98	-110	-110	-110
8400-8600	-110	-110	-110	-110	-110	-110	-110

8600-11900	-110	-110	-110	-110	-110	-110	-98
11900-30M	-110	-110	-110	-110	-110	-110	-110

**Table 23 - DS Wideband Bit Swapping Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) Set up the loop simulator to: <ul style="list-style-type: none"> <li>700 feet 26AWG cable for North America</li> <li>or</li> <li>300 m PE 0.4mm for Europe</li> </ul> </li> <li>(3) Set the noise generator at VTU-O side to B-AWGN noise.</li> <li>(4) Set the noise generator at VTU-R side to B-DS2 noise.</li> <li>(5) The VDSL2 profile line combination SHALL be configured as follows: <ol style="list-style-type: none"> <li>a. For European VDSL2overPOTS: <ul style="list-style-type: none"> <li>BA17ade_RA_I_150_150</li> <li>BA30a_RA_I_150_150</li> <li>BA17a0_RA_R-17/2/41_150_150</li> </ul> </li> <li>or</li> <li>b. For European VDSL2overISDN: <ul style="list-style-type: none"> <li>BB12a_RA_I_150_150</li> <li>BB17a_RA_I_150_150</li> <li>BB30a_RA_I_150_150</li> </ul> </li> </ol> </li> <li>(6) SRA SHALL be disabled.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Connect the VTU-O and VTU-R. Wait for the modems to sync.</li> <li>(2) Wait for 1 minute after initialization.</li> <li>(3) Record the bit allocation BITSpsds in the Downstream direction. Document it as BITSpsds_Old.</li> <li>(4) Change the noise at VTU-R side to B-AWGN.</li> <li>(5) Wait 30 seconds for the bit-swapping to execute.</li> <li>(6) Change the noise at VTU-R side to B-DS1a noise.</li> <li>(7) Wait for 30 seconds for the bit-swapping to execute.</li> <li>(8) Change the noise at VTU-R side to B-DS1b noise.</li> <li>(9) Wait for 30 seconds for the bit-swapping to execute.</li> <li>(10) Record the bit allocation, BITSpsds, in the Downstream direction. Document it as BITSpsds_New.</li> <li>(11) Start a CRC measurement for 1 minute in the downstream direction.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) There SHALL be no retrain during the test.</li> <li>(2) BITSpsds_New recorded in MOP(10) SHALL differ from the bit allocation, BITSpsds_Old, in MOP(3), with band DS1 showing a decreased number of bits, and band DS2 showing an increased number of bits.</li> <li>(3) The number of measured CRCs during the measurement period in MOP(11) SHALL be <math>\leq 1</math>.</li> </ol>

**Table 24 - US Wideband Bit Swapping Test**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) Set up the loop simulator to: 700 feet 26AWG cable for North America or 300 m PE 0.4mm for Europe</p> <p>(3) Set the noise generator at VTU-R side to B-AWGN noise.</p> <p>(4) Set the noise generator at VTU-O side to B-US2 noise.</p> <p>(5) The VDSL2 profile line combination SHALL be configured as follows:</p> <p style="padding-left: 20px;">a. For European VDSL2overPOTS BA17ade_RA_I_150_150 BA30a_RA_I_150_150 BA17a0_RA_R-17/2/41_150_150</p> <p style="padding-left: 20px;">or</p> <p style="padding-left: 20px;">a. For European VDSL2overISDN BB12a_RA_I_150_150 BB17a_RA_I_150_150 BB30a_RA_I_150_150</p> <p>(6) SRA SHALL be disabled.</p>
<b>Method of Procedure</b>	<p>(1) Connect the VTU-O and VTU-R. Wait for the modems to sync.</p> <p>(2) Wait for 1 minute after initialization.</p> <p>(3) Record the bit allocation BITSpsus in the Upstream direction. Document it as BITSpsus_Old.</p> <p>(4) Change the noise at VTU-O side to B-AWGN.</p> <p>(5) Wait 30 seconds for the bit-swapping to execute.</p> <p>(6) Change the noise at VTU-O side to B-US1a noise.</p> <p>(7) Wait 30 seconds for the bit-swapping to execute.</p> <p>(8) Change the noise at VTU-O side to B-US1b noise.</p> <p>(9) Wait for 30 seconds for the bit-swapping to execute.</p> <p>(10) Record the bit allocation BITSpsus in the Upstream direction. Document it as BITSpsus_New.</p> <p>(11) Start a CRC measurement for 1 minute in the Upstream direction.</p>
<b>Expected Result</b>	<p>(1) There SHALL be no retrain during the test.</p> <p>(2) BITSpsus_New recorded in MOP(10) SHALL differ from BITSpsus_Old in MOP(3), with band US1 showing a decreased number of bits, and band US2 showing an increased number of bits.</p> <p>(3) The number of measured CRCs during the measurement period in MOP(11) SHALL be <math>\leq 1</math>.</p>

#### 5.4.4 Seamless Rate Adaptation Test (Optional)

The purpose of this test is to verify the functionality of the SRA. It includes the type 3 OLR test without interleaving (SRA fast mode test) and with dynamic change of interleaving depth (SRA interleaved mode with DCID test), as well as type 5 OLR test without interleaving (SRA retransmission mode test) and with interleaving (SRA retransmission mode with interleaving test).

This test is divided into 4 sub-tests (each being split into downstream and upstream test):

1. SRA fast mode
2. SRA interleaved mode with DCID

3. SRA retransmission test
4. SRA retransmission with interleaving

For each sub-test to pass, both downstream and upstream tests SHALL be passed.

Sub-test 1 is REQUIRED for the SUT supporting type 3 OLR without interleaving to pass the SRA test.

Sub-test 2 is REQUIRED for the SUT supporting type 3 OLR and dynamic change of interleaving depth (DCID) to pass the SRA test. NOTE 1: Sub-test 1 MAY be run with this SUT.

Sub-test 3 is REQUIRED for the SUT supporting type 5 OLR to pass the SRA test.

Sub-test 4 is REQUIRED for the SUT supporting type 5 OLR and interleaving to pass the SRA test. NOTE 2: Sub-test 3 MAY be run with this SUT.

This test SHALL be performed with the following SRA parameter set:

**Table 25 - SRA Configuration**

Rate Adaptation Mode (RA-MODEds)	DYNAMIC
Downstream Target Noise Margin (TARSNRMds)	6dB
Downstream Downshift Noise Margin (RA-DSNRMds)	3dB
Downstream Minimum Downshift Rate Adaptation Interval (RA-DTIMEds)	10sec
Downstream Upshift Noise Margin (RA-USNRMds)	9dB
Downstream Minimum Upshift Rate Adaptation Interval (RA-UTIMEds)	30sec
Rate Adaptation Mode (RA-MODEus)	DYNAMIC
Upstream Target Noise Margin (TARSNRMus)	6dB
Upstream Downshift Noise Margin (RA-DSNRMus)	3dB
Upstream Minimum Downshift Rate Adaptation Interval (RA-DTIMEus)	10sec
Upstream Upshift Noise Margin (RA-USNRMus)	9dB
Upstream Minimum Upshift Rate Adaptation Upstream (RA-UTIMEus)	30sec

#### 5.4.4.1 SRA fast mode test

**Table 26 - SRA fast mode test - Downstream**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT in RA_F_150_150 specific line-setting (see Section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(3) Configure the SRA settings as indicated in Table 25.</li> <li>(4) Connect VTU-O and VTU-R to <ol style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ol> </li> </ol>
---------------------------	--

<p><b>Method of Procedure</b></p>	<p>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</p> <p>(1) Force a new initialization and wait for modems to sync.  (2) Wait for 1 minute for bitswaps to settle.  (3) Check reported margin. Record the reported DS net data rate as rate_ds.</p> <p style="text-align: center;"><i>Downshift functionality sub-test</i></p> <p>(4) Increase the noise power level by 1 dB at VTU-R side only.  (5) Wait for 1 minute, then check reported DS margin.  (6) Repeat MOP(4) and MOP(5) until: RA-DSNRMs &lt; DS reported margin <math>\leq</math> RA-DSNRMs + 1.5dB.  (7) Increase the noise power level by 3 dB at VTU-R side only.  (8) Wait for (RA-DTIMEs + 30) seconds for SRA to settle.  (9) Record the reported DS margin as SRA_reported_margin_downshift_ds. Record the DS net data rate as SRA_downshift_rate_ds.  (10) Execute BER test for 2 minutes.  (11) Record the DS CRC and DS SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts. Record the estimated downshift_BER_ds (See Section 4.6 on BER).</p> <p style="text-align: center;"><i>Upshift functionality sub-test</i></p> <p>(12) Decrease the noise power level by 1 dB at VTU-R side only.  (13) Wait for 1 minute, then check the reported DS margin.  (14) Repeat MOP(12) and MOP(13) until: RA-USNRMs - 1.5dB <math>\leq</math> reported DS margin &lt; RA-USNRMs.  (15) Decrease the noise power level by 3 dB at VTU-R side only.  (16) Wait for (RA-UTIMEs + 30) seconds for SRA to settle.  (17) Record the reported DS margin as SRA_reported_margin_upshift_ds. Record the reported DS net data rate as SRA_upshift_rate_ds.  (18) Execute BER test for 2 minutes.  (19) Record the DS CRC and DS SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts. Record the estimated upshift_BER_ds (See Section 4.6 on BER).</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur during the test.  (2) SRA_reported_margin_downshift_ds <math>\geq</math> RA-DSNRMs + 1 dB.  (3) SRA_reported_margin_upshift_ds <math>\leq</math> RA-USNRMs - 1dB.  (4) SRA_downshift_rate_ds &lt; rate_ds;  (5) SRA_upshift_rate_ds &gt; SRA_downshift_rate_ds.  (6) Estimated downshift_BER_ds and upshift_BER_ds SHALL NOT exceed <math>10^{-7}</math>.  (7) No DS SES SHALL be reported.</p>

**Table 27 - SRA fast mode test - Upstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT in RA_F_150_150 specific line-setting (see Section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Configure the SRA settings as indicated in Table 25.</p> <p>(4) Connect VTU-O and VTU-R to</p> <ul style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ul> <p>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</p>
<b>Method of Procedure</b>	<p>(1) Force a new initialization and wait for modems to sync.</p> <p>(2) Wait for 1 minute for bitswaps to settle.</p> <p>(3) Check the reported margin. Record the reported US net data rate as rate_us.</p> <p style="text-align: center;"><b><i>Downshift functionality sub-test</i></b></p> <p>(4) Increase the noise power level by 1 dB at VTU-O side only.</p> <p>(5) Wait for 1 minute, then check reported US margin.</p> <p>(6) Repeat MOP(4) and MOP(5) until: RA-DSNRMus &lt; reported US margin <math>\leq</math> RA-DSNRMus + 1.5dB.</p> <p>(7) Increase the noise power level by 3 dB at VTU-O side only.</p> <p>(8) Wait for (RA-DTIMEus + 30) seconds for SRA to settle.</p> <p>(9) Record the reported US margin as SRA_reported_margin_downshift_us. Record the reported US net data rate as SRA_downshift_rate_us.</p> <p>(10) Execute BER test for 2 minutes.</p> <p>(11) Record the US CRC and US SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts. Record the estimated downshift_BER_us (See Section 4.6 on BER).</p> <p style="text-align: center;"><b><i>Upshift functionality sub-test</i></b></p> <p>(12) Decrease the noise power level by 1 dB at VTU-O side only.</p> <p>(13) Wait for 1 minute, then check the reported US margin.</p> <p>(14) Repeat MOP(12) and MOP(13) until: RA-USNRMus - 1.5dB <math>\leq</math> reported US margin &lt; RA-USNRMus.</p> <p>(15) Decrease the noise power level by 3 dB at VTU-O side only.</p> <p>(16) Wait for (RA-UTIMEus + 30) seconds for SRA to settle.</p> <p>(17) Record the reported US margin as SRA_reported_margin_upshift_us. Record the reported US net data rate as SRA_upshift_rate_us.</p> <p>(18) Execute BER test for 2 minutes.</p> <p>(19) Record the US CRC and US SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference</p>



	between these two counts. Record the estimated upshift_BER_us (See Section 4.6 on BER).
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) No retrain SHALL occur during the test.</li> <li>(2) <math>SRA\_reported\_margin\_downshift\_us \geq RA\_DSNRMus + 1dB</math>.</li> <li>(3) <math>SRA\_reported\_margin\_upshift\_us \leq RA\_USNRMus - 1dB</math>.</li> <li>(4) <math>SRA\_downshift\_rate\_us &lt; rate\_us</math>.</li> <li>(5) <math>SRA\_upshift\_rate\_us &gt; SRA\_downshift\_rate\_us</math>.</li> <li>(6) The estimated BER SHALL NOT exceed <math>10^{-7}</math>.</li> <li>(7) No US SES SHALL be reported.</li> </ol>

#### 5.4.4.2 SRA interleaved mode test with DCID

**Table 28 - SRA interleaved mode test with DCID – Downstream**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT in RA_I_150_150 specific line-setting (see Section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(3) Configure the SRA settings as indicated in Table 25.</li> <li>(4) Connect VTU-O and VTU-R to <ol style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ol> </li> <li>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Force a new initialization and wait for modems to sync.</li> <li>(2) Wait for 1 minute for bitswaps to settle.</li> <li>(3) Check reported margin. Record the reported DS net data rate as rate_ds.</li> <li>(4) Record the DS interleaving depth as downshift_ID_ds_init.</li> </ol> <p style="text-align: center;"><b><i>SRA Downshift functionality sub-test</i></b></p> <ol style="list-style-type: none"> <li>(5) Increase the noise power level by 1 dB at VTU-R side only.</li> <li>(6) Wait for 1 minute, then check reported DS margin.</li> <li>(7) Repeat MOP(5) and MOP(6) until: <math>RA\_DSNRMds &lt; DS</math> reported margin <math>\leq RA\_DSNRMds + 1.5dB</math>.</li> <li>(8) Increase the noise power level by 3 dB at VTU-R side only.</li> <li>(9) Wait for <math>(RA\_DTIMEds + 30)</math> seconds for SRA to settle.</li> <li>(10) Record: <ul style="list-style-type: none"> <li>the reported DS margin as SRA_reported_margin_downshift_ds,</li> <li>the reported DS net data rate as SRA_downshift_rate_ds,</li> <li>the reported DS interleaving depth as downshift_ID_ds,</li> <li>the reported actual delay as downshift_delay_ds,</li> <li>the reported actual INP as downshift_INP_ds.</li> </ul> </li> <li>(11) If the downshift_ID_ds is equal to the downshift_ID_ds_init, repeat MOP(5) to MOP(10).</li> <li>(12) Execute BER test for 2 minutes.</li> <li>(13) Record the DS CRC and DS SES counts at the start and the end of</li> </ol>

	<p>the BER test. Actual number of CRCs and SESs is the difference between these two counts. Report the estimated downshift_BER_ds (See Section 4.6 on BER).</p> <p style="text-align: center;"><b><i>SRA Upshift functionality sub-test</i></b></p> <p>(14) Decrease the noise power level by 1 dB at VTU-R side only.          (15) Wait for 1 minute, then check the reported margin.          (16) Repeat MOP(14) and MOP(15) until: <math>RA-USNRMds - 1.5dB \leq DS</math> reported margin <math>&lt; RA-USNRMds</math>.          (17) Decrease the noise power level by 3 dB at VTU-R side only.          (18) Wait for (RA-UTIMEs + 30) seconds for SRA to settle.          (19) Record:              the reported DS margin as SRA_reported_margin_upshift_ds,              the reported DS net data rate as SRA_upshift_rate_ds,              the reported DS interleaving depth as upshift_ID_ds,              the reported actual delay as upshift_delay_ds,              the reported actual INP as upshift_INP_ds.          (20) If the upshift_ID_ds is equal to downshift_ID_ds, repeat MOP(14) to MOP(19).          (21) Execute BER test for 2 minutes.          (22) Record the DS CRC and DS SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts. Record the estimated upshift_BER_ds (See Section 4.6 on BER).</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur during the test.          (2) <math>SRA\_reported\_margin\_downshift\_ds \geq RA-DSNRMds + 1</math> dB.          (3) <math>SRA\_reported\_margin\_upshift\_ds \leq RA-USNRMds - 1</math>dB.          (4) <math>SRA\_downshift\_rate\_ds &lt; downshift\_rate\_ds</math>.          (5) <math>SRA\_upshift\_rate\_ds &gt; SRA\_downshift\_rate\_ds</math>.          (6) downshift_ID_ds SHALL differ from downshift_ID_ds_init.          (7) upshift_ID_ds SHALL differ from downshift_ID_ds.          (8) Estimated downshift_BER_ds and upshift_BER_ds SHALL NOT exceed <math>10^{-7}</math>.          (9) No DS SES SHALL be reported.          (10) <math>downshift\_delay\_ds \leq</math> Maximum Interleaving Delay of the profile.          (11) <math>upshift\_delay\_ds \leq</math> Maximum Interleaving Delay of the profile.          (12) <math>downshift\_INP\_ds \geq INPMIN</math> (INPMIN8 for 30MHz profiles).          (13) <math>upshift\_INP\_ds \geq INPMIN</math> (INPMIN8 for 30MHz profiles).</p>

**Table 29 - SRA interleaved mode test with DCID – Upstream**

<p><b>Test Configuration</b></p>	<p>(1) See Section 4.1 for the test configuration.          (2) As per VDSL2 band-profile to be tested, configure the SUT in RA_I_150_150 specific line-setting (see Section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.          (3) Configure the SRA settings as indicated in Table 25.          (4) Connect VTU-O and VTU-R to              a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</p>
----------------------------------	--

	<p>or</p> <p>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</p> <p>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</p>
<p><b>Method of Procedure</b></p>	<p>(1) Force a new initialization and wait for modems to sync.</p> <p>(2) Wait for 1 minute for bitswaps to settle.</p> <p>(3) Check reported margin. Record the reported US net data rate as rate_us.</p> <p>(4) Record the US interleaving depth as downshift_ID_us_init.</p> <p><b><i>SRA Downshift functionality sub-test</i></b></p> <p>(5) Increase the noise power level by 1 dB at VTU-O side only.</p> <p>(6) Wait for 1 minute, then check reported US margin.</p> <p>(7) Repeat MOP(5) and MOP(6) until: RA-DSNRMus &lt; US reported margin <math>\leq</math> RA-DSNRMus + 1.5dB.</p> <p>(8) Increase the noise power level by 3 dB at VTU-O side only.</p> <p>(9) Wait for (RA-DTIMEus + 30) seconds for SRA to settle.</p> <p>(10) Record: the reported US margin as SRA_reported_margin_downshift_us, the reported US net data rate as SRA_downshift_rate_us, the reported US interleaving depth as downshift_ID_us, the reported actual delay as downshift_delay_us, the reported actual INP as downshift_INP_us.</p> <p>(11) If the downshift_ID_us is equal to the downshift_ID_us_init, repeat MOP(5) to MOP(10).</p> <p>(12) Execute BER test for 2 minutes.</p> <p>(13) Record the US CRC and US SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts. Record the estimated downshift_BER_us (See Section 4.6 on BER).</p> <p><b><i>SRA Upshift functionality sub-test</i></b></p> <p>(14) Decrease the noise power level by 1 dB at VTU-O side only.</p> <p>(15) Wait for 1 minute, then check the reported margin</p> <p>(16) Repeat MOP(14) and MOP(15) until: RA-USNRMus - 1.5dB <math>\leq</math> US reported margin &lt; RA-USNRMus.</p> <p>(17) Decrease the noise power level by 3 dB at VTU-O side only.</p> <p>(18) Wait for (RA-UTIMEus + 30) seconds for SRA to settle.</p> <p>(19) Record: the reported US margin as SRA_reported_margin_upshift_us, the reported US net data rate as SRA_upshift_rate_us, the reported US interleaving depth as upshift_ID_us, the reported actual delay as upshift_delay_us, the reported actual INP as upshift_INP_us.</p> <p>(20) If the upshift_ID_us is equal to downshift_ID_us, repeat MOP(14) to MOP(19).</p> <p>(21) Execute BER test for 2 minutes.</p> <p>(22) Record the US CRC and US SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts. Record the estimated upshift_BER_us (See Section 4.6 on BER).</p>

<p><b>Expected Result</b></p>	<ul style="list-style-type: none"> <li>(1) No retrain SHALL occur during the test.</li> <li>(2) <math>SRA\_reported\_margin\_downshift\_us \geq RA-DSNRMus + 1\text{ dB}</math>.</li> <li>(3) <math>SRA\_reported\_margin\_upshift\_us \leq RA-USNRMus - 1\text{ dB}</math>.</li> <li>(4) <math>SRA\_downshift\_rate\_us &lt; downshift\_rate\_us</math>.</li> <li>(5) <math>SRA\_upshift\_rate\_us &gt; SRA\_downshift\_rate\_us</math>.</li> <li>(6) <math>downshift\_ID\_us</math> SHALL differ from <math>downshift\_ID\_us\_init</math>.</li> <li>(7) <math>upshift\_ID\_us</math> SHALL differ from <math>downshift\_ID\_us</math>.</li> <li>(8) Estimated <math>downshift\_BER\_us</math> and <math>upshift\_BER\_us</math> SHALL NOT exceed <math>10^{-7}</math>.</li> <li>(9) No US SES SHALL be reported.</li> <li>(10) <math>downshift\_delay\_us \leq</math> Maximum Interleaving Delay of the profile.</li> <li>(11) <math>upshift\_delay\_us \leq</math> Maximum Interleaving Delay of the profile.</li> <li>(12) <math>downshift\_INP\_us \geq INPMIN</math> (INPMIN8 for 30MHz profiles).</li> <li>(13) <math>upshift\_INP\_us \geq INPMIN</math> (INPMIN8 for 30MHz profiles).</li> </ul>
-------------------------------	--

**5.4.4.3 SRA retransmission test**

**Table 30 - SRA retransmission test – Downstream**

<p><b>Test Configuration</b></p>	<ul style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT in the retransmission specific line-setting (see Section 4.2.2.2). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(3) Configure the SRA settings as indicated in Table 25.</li> <li>(4) Connect VTU-O and VTU-R to             <ul style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ul> </li> <li>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</li> </ul>
<p><b>Method of Procedure</b></p>	<ul style="list-style-type: none"> <li>(1) Force a new initialization and wait for modems to sync.</li> <li>(2) Wait for 1 minute for bitswaps to settle.</li> <li>(3) Check reported margin. Record the reported DS net data rate as <math>rate\_ds</math>.</li> </ul> <p style="text-align: center;"><b><i>SRA Downshift functionality sub-test</i></b></p> <ul style="list-style-type: none"> <li>(4) Increase the noise power level by 1 dB at VTU-R side only.</li> <li>(5) Wait for 1 minute, then check reported DS margin.</li> <li>(6) Repeat MOP(5) and MOP(6) until: <math>RA-DSNRMds &lt; DS\ reported\ margin \leq RA-DSNRMds + 1.5\text{ dB}</math>.</li> <li>(7) Increase the noise power level by 3 dB at VTU-R side only.</li> <li>(8) Wait for <math>(RA-DTImEds + 30)</math> seconds for SRA to settle.</li> <li>(9) Record the reported DS margin as <math>SRA\_reported\_margin\_downshift\_ds</math>. Record the reported DS net data rate as <math>SRA\_downshift\_rate\_ds</math>.</li> <li>(10) Execute an CV, ES and SES counter test for 2 minutes.</li> <li>(11) Record the DS CV, ES and SES counts at the start and the end of the</li> </ul>

	<p>counter test. Actual number of CVs (CV_downshift_ds), ESs (ES_downshift_ds) and SESs (SES_downshift_ds) is the difference between these two counts.</p> <p><b><i>SRA Upshift functionality sub-test</i></b></p> <p>(12) Decrease the noise power level by 1 dB at VTU-R side only.                  (13) Wait for 1 minute, then check the reported margin.                  (14) Repeat MOP(12) and MOP(13) until: RA-USNRMds - 1.5dB ≤ DS reported margin &lt; RA-USNRMds.                  (15) Decrease the noise power level by 3 dB at VTU-R side only.                  (16) Wait for (RA-UTIMEds + 30) seconds for SRA to settle.                  (17) Record the reported DS margin as SRA_reported_margin_upshift_ds. Record the reported DS net data rate as SRA_upshift_rate_ds.                  (18) Execute an CV, ES and SES counter test for 2 minutes.                  (19) Record the DS CV, ES and SES counts at the start and the end of the ES test. Actual number of CVs (CV_upshift_ds), ESs (ES_upshift_ds) and SESs (SES_upshift_ds) is the difference between these two counts.</p>
<b>Expected Result</b>	<p>(1) No retrain SHALL occur during the test.                  (2) SRA_reported_margin_downshift_ds ≥ RA-DSNRMds + 1 dB.                  (3) SRA_reported_margin_upshift_ds ≤ RA-USNRMds - 1dB.                  (4) SRA_downshift_rate_ds &lt; downshift_rate_ds.                  (5) SRA_upshift_rate_ds &gt; SRA_downshift_rate_ds.                  (6) No ES_downshift_ds SHALL be reported.                  (7) No ES_upshift_ds SHALL be reported .                  (8) No CV_downshift_ds SHALL be reported.                  (9) No CV_upshift_ds SHALL be reported.                  (10) No SES_downshift_ds SHALL be reported.                  (11) No SES_upshift_ds SHALL be reported.</p>

**Table 31 - SRA retransmission test – Upstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.                  (2) As per VDSL2 band-profile to be tested, configure the SUT in retransmission specific line-setting (see Section 4.2.2.2). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.                  (3) Configure the SRA settings as indicated in Table 25.                  (4) Connect VTU-O and VTU-R to                  c. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles                  or                  d. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles                  (5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</p>
<b>Method of Procedure</b>	<p>(1) Force a new initialization and wait for modems to sync.                  (2) Wait for 1 minute for bitswaps to settle.                  (3) Check reported margin. Record the reported US net data rate as rate_us.</p>

	<p><b><i>SRA Downshift functionality sub-test</i></b></p> <p>(4) Increase the noise power level by 1 dB at VTU-O side only.  (5) Wait for 1 minute, then check reported US margin.  (6) Repeat MOP(5) and MOP(6) until: RA-DSNRMus &lt; US reported margin ≤ RA-DSNRMus + 1.5dB.  (7) Increase the noise power level by 3 dB at VTU-O side only.  (8) Wait for (RA-DTIMEus + 30) seconds for SRA to settle.  (9) Record the reported US margin as SRA_reported_margin_downshift_us. Record the reported US net data rate as SRA_downshift_rate_us.  (10) Execute an CV, ES and SES counter test for 2 minutes.  (11) Record the US CV, ES and SES counts at the start and the end of the counter test. Actual number of CVs (CV_downshift_us), ESs (ES_downshift_us) and SESs (SES_downshift_us) is the difference between these two counts.</p> <p><b><i>SRA Upshift functionality sub-test</i></b></p> <p>(12) Decrease the noise power level by 1 dB at VTU-O side only.  (13) Wait for 1 minute, then check the reported margin  (14) Repeat MOP(12) and MOP(13) until: RA-USNRMus - 1.5dB ≤ US reported margin &lt; RA-USNRMus.  (15) Decrease the noise power level by 3 dB at VTU-O side only.  (16) Wait for (RA-UTIMEus + 30) seconds for SRA to settle.  (17) Record the reported US margin as SRA_reported_margin_upshift_us. Record the reported the US net data rate as SRA_upshift_rate_us.  (18) Execute an CV, ES and SES counter test for 2 minutes.  (19) Record the US CV, ES and SES counts at the start and the end of the ES test. Actual number of CVs (CV_upshift_us), ESs (ES_upshift_us) and SESs (SES_upshift_us) is the difference between these two counts.</p>
<b>Expected Result</b>	<p>(1) No retrain SHALL occur during the test.  (2) SRA_reported_margin_downshift_us ≥ RA-DSNRMus + 1 dB.  (3) SRA_reported_margin_upshift_us ≤ RA-USNRMus - 1dB.  (4) SRA_downshift_rate_us &lt; downshift_rate_us.  (5) SRA_upshift_rate_us &gt; SRA_downshift_rate_us.  (6) No ES_downshift_us SHALL be reported.  (7) No ES_upshift_us SHALL be reported .  (8) No CV_downshift_us SHALL be reported.  (9) No CV_upshift_us SHALL be reported.  (10) No SES_downshift_us SHALL be reported.  (11) No SES_upshift_us SHALL be reported.</p>

**5.4.4.4 SRA retransmission with interleaving test**

**Table 32 - SRA retransmission with interleaving test– Downstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.  (2) As per VDSL2 band-profile to be tested, configure the SUT in retransmission specific line-setting (see Section 4.2.2.2). If, for the</p>
---------------------------	--

	<p>specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Configure the SRA settings as indicated in Table 25.</p> <p>(4) Connect VTU-O and VTU-R to</p> <ol style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ol> <p>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</p>
<p><b>Method of Procedure</b></p>	<p>(1) Force a new initialization and wait for modems to sync.</p> <p>(2) Wait for 1 minute for bitswaps to settle.</p> <p>(3) Check reported margin. Record the reported DS net data rate as rate_ds.</p> <p>(4) Record the DS interleaving depth as downshift_ID_ds_init.</p> <p style="text-align: center;"><b><i>SRA Downshift functionality sub-test</i></b></p> <p>(5) Increase the noise power level by 1 dB at VTU-R side only.</p> <p>(6) Wait for 1 minute, then check reported DS margin.</p> <p>(7) Repeat MOP(5) and MOP(6) until: RA-DSNRMds &lt; DS reported margin ≤ RA-DSNRMds + 1.5dB.</p> <p>(8) Increase the noise power level by 3 dB at VTU-R side only.</p> <p>(9) Wait for (RA-DTIMEds + 30) seconds for SRA to settle.</p> <p>(10) Record:  the reported DS margin as SRA_reported_margin_downshift_ds,  the reported DS net data rate as SRA_downshift_rate_ds,  the reported DS interleaving depth as downshift_ID_ds,  the reported actual DS downshift_INP_REIN_ds,  the reported actual DS downshift_INP_SHINE_ds.</p> <p>(11) If the downshift_ID_ds is equal to the downshift_ID_ds_init, repeat MOP(5) to MOP(10).</p> <p>(12) Execute an CV, ES and SES counter test for 2 minutes.</p> <p>(13) Record the DS CV, ES and SES counts at the start and the end of the counter test. Actual number of CVs (CV_downshift_ds), ESs (ES_downshift_ds) and SESs (SES_downshift_ds) is the difference between these two counts.</p> <p style="text-align: center;"><b><i>SRA Upshift functionality sub-test</i></b></p> <p>(14) Decrease the noise power level by 1 dB at VTU-R side only.</p> <p>(15) Wait for 1 minute, then check the reported margin</p> <p>(16) Repeat MOP(14) and MOP(15) until: RA-USNRMds - 1.5dB ≤ DS reported margin &lt; RA-USNRMds.</p> <p>(17) Decrease the noise power level by 3 dB at VTU-R side only.</p> <p>(18) Wait for (RA-UTIMEds + 30) seconds for SRA to settle.</p> <p>(19) Record:  the reported DS margin as SRA_reported_margin_upshift_ds,  the reported DS net data rate as SRA_upshift_rate_ds,  the reported DS interleaving depth as upshift_ID_ds,</p>

	<p>the reported actual DS upshift_INP_REIN_ds, the reported actual DS upshift_INP_SHINE_ds.</p> <p>(20) If the upshift_ID_ds is equal to downshift_ID_ds, repeat MOP(14) to MOP(19).</p> <p>(21) Execute an CV, ES and SES counter test for 2 minutes.</p> <p>(22) Record the DS CV, ES and SES counts at the start and the end of the counter test. Actual number of CVs (CV_upshift_ds), ESs (ES_upshift_ds) and SESs (SES_upshift_ds) is the difference between these two counts.</p>
<b>Expected Result</b>	<p>(1) No retrain SHALL occur during the test.</p> <p>(2) <math>SRA\_reported\_margin\_downshift\_ds \geq RA-DSNRMs + 1 \text{ dB}</math>.</p> <p>(3) <math>SRA\_reported\_margin\_upshift\_ds \leq RA-USNRMs - 1\text{dB}</math>.</p> <p>(4) <math>SRA\_downshift\_rate\_ds &lt; downshift\_rate\_ds</math>.</p> <p>(5) <math>SRA\_upshift\_rate\_ds &gt; SRA\_downshift\_rate\_ds</math>.</p> <p>(6) downshift_ID_ds SHALL differ from downshift_ID_ds_init.</p> <p>(7) upshift_ID_ds SHALL differ from downshift_ID_ds.</p> <p>(8) No ES_downshift_ds SHALL be reported.</p> <p>(9) No ES_upshift_ds SHALL be reported .</p> <p>(10) No CV_downshift_ds SHALL be reported.</p> <p>(11) No CV_upshift_ds SHALL be reported.</p> <p>(12) No SES_downshift_ds SHALL be reported.</p> <p>(13) No SES_upshift_ds SHALL be reported.</p> <p>(14) <math>downshift\_INP\_REIN\_ds \geq INPMIN\_REIN\_RTX</math> (INPMIN8_REIN_RTX for 30MHz profiles).</p> <p>(15) <math>downshift\_INP\_SHINE\_ds \geq INPMIN\_SHINE\_RTX</math> (INPMIN8_SHINE_RTX for 30MHz profiles).</p> <p>(16) <math>upshift\_INP\_REIN\_ds \geq INPMIN\_SHINE\_RTX</math> (INPMIN8_REIN_RTX for 30MHz profiles).</p> <p>(17) <math>upshift\_INP\_SHINE\_ds \geq INPMIN\_SHINE\_RTX</math> (INPMIN8_SHINE_RTX for 30MHz profiles).</p>

**Table 33 - SRA retransmission with interleaving test– Upstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT in retransmission specific line-setting (see Section 4.2.2.2). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Configure the SRA settings as indicated in Table 25.</p> <p>(4) Connect VTU-O and VTU-R to</p> <p style="padding-left: 20px;">a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</p> <p style="padding-left: 20px;">or</p> <p style="padding-left: 20px;">b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</p> <p>(5) Inject -110dBm/Hz AWGN noise at both the VTU-O and VTU-R side.</p>
<b>Method of Procedure</b>	<p>(1) Force a new initialization and wait for modems to sync.</p> <p>(2) Wait for 1 minute for bitswaps to settle.</p> <p>(3) Check reported margin. Record the reported US net data rate as rate_us.</p> <p>(4) Record the US interleaving depth as downshift_ID_us_init.</p>



	<p><b><i>SRA Downshift functionality sub-test</i></b></p> <p>(5) Increase the noise power level by 1 dB at VTU-O side only.</p> <p>(6) Wait for 1 minute, then check reported US margin.</p> <p>(7) Repeat MOP(5) and MOP(6) until: <math>RA-DSNRMus &lt; US \text{ reported margin} \leq RA-DSNRMus + 1.5dB</math>.</p> <p>(8) Increase the noise power level by 3 dB at VTU-O side only.</p> <p>(9) Wait for <math>(RA-DTIMEus + 30)</math> seconds for SRA to settle.</p> <p>(10) Record:  the reported US margin as SRA_reported_margin_downshift_us,  the reported US net data rate as SRA_downshift_rate_us,  the reported US interleaving depth as downshift_ID_us,  the reported actual US downshift_INP_REIN_us,  the reported actual US downshift_INP_SHINE_us.</p> <p>(11) If the downshift_ID_us is equal to the downshift_ID_us_init, repeat MOP(5) to MOP(10).</p> <p>(12) Execute an CV, ES and SES counter test for 2 minutes.</p> <p>(13) Record the US CV, ES and SES counts at the start and the end of the counter test. Actual number of CVs (CV_downshift_us), ESs (ES_downshift_us) and SESs (SES_downshift_us) is the difference between these two counts.</p> <p><b><i>SRA Upshift functionality sub-test</i></b></p> <p>(14) Decrease the noise power level by 1 dB at VTU-O side only.</p> <p>(15) Wait for 1 minute, then check the reported margin</p> <p>(16) Repeat MOP(14) and MOP(15) until: <math>RA-USNRMus - 1.5dB \leq US \text{ reported margin} &lt; RA-USNRMus</math>.</p> <p>(17) Decrease the noise power level by 3 dB at VTU-O side only.</p> <p>(18) Wait for <math>(RA-UTIMEus + 30)</math> seconds for SRA to settle.</p> <p>(19) Record:  the reported US margin as SRA_reported_margin_upshift_us,  the reported US net data rate as SRA_upshift_rate_us,  the reported US interleaving depth as upshift_ID_us,  the reported actual US upshift_INP_REIN_us,  the reported actual US upshift_INP_SHINE_us.</p> <p>(20) If the upshift_ID_us is equal to downshift_ID_us, repeat MOP(14) to MOP(19).</p> <p>(21) Execute an CV, ES and SES counter test for 2 minutes.</p> <p>(22) Record the US CV, ES and SES counts at the start and the end of the counter test. Actual number of CVs (CV_upshift_us), ESs (ES_upshift_us) and SESs (SES_upshift_us) is the difference between these two counts.</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur during the test.</p> <p>(2) <math>SRA\_reported\_margin\_downshift\_us \geq RA-DSNRMus + 1 \text{ dB}</math>.</p> <p>(3) <math>SRA\_reported\_margin\_upshift\_us \leq RA-USNRMus - 1dB</math>.</p> <p>(4) <math>SRA\_downshift\_rate\_us &lt; downshift\_rate\_us</math>.</p> <p>(5) <math>SRA\_upshift\_rate\_us &gt; SRA\_downshift\_rate\_us</math>.</p> <p>(6) downshift_ID_us SHALL differ from downshift_ID_us_init.</p> <p>(7) upshift_ID_us SHALL differ from downshift_ID_us.</p> <p>(8) No ES_downshift_us SHALL be reported.</p>

	<p>(9) No ES_upshift_us SHALL be reported .</p> <p>(10) No CV_downshift_us SHALL be reported.</p> <p>(11) No CV_upshift_us SHALL be reported.</p> <p>(12) No SES_downshift_us SHALL be reported.</p> <p>(13) No SES_upshift_us SHALL be reported.</p> <p>(14) downshift_INP_REIN_us <math>\geq</math> INPMIN_REIN_TX (INPMIN8_REIN_RTX for 30MHz profiles).</p> <p>(15) downshift_INP_SHINE_us <math>\geq</math> INPMIN_SHINE_TX (INPMIN8_SHINE_RTX for 30MHz profiles).</p> <p>(16) upshift_INP_REIN_us <math>\geq</math> INPMIN_REIN_TX (INPMIN8_REIN_RTX for 30MHz profiles).</p> <p>(17) upshift_INP_SHINE_us <math>\geq</math> INPMIN_SHINE_TX (INPMIN8_SHINE_RTX for 30MHz profiles).</p>
--	---

#### 5.4.5 SOS Test (Optional)

The purpose of this test is to verify that the optional OLR mechanism SOS is implemented according to the directions of Amendment 3 of ITU-T G.993.2. The test SHALL apply to the SOS functionality with enabled ROC (robust overhead channel).

NOTE – For the following test configuration, the MIN-SOS-BR is configured to be greater than Min-NDR.

**Table 34 – SOS Test in the Downstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) According to the band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see Section 4.2.3). If for the specific band-profile, profile-line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Configure the following settings:</p> <ul style="list-style-type: none"> <li>a. DS Minimum SOS Bit Rate (MIN-SOS-BR-ds): 20000kbps</li> <li>b. DS SOS time Window (SOS-TIME-ds): 64ms</li> <li>c. DS Minimum Percentage of Degraded Tones (SOS-NTONES-ds): 50</li> <li>d. DS Minimum Number of normalized CRC anomalies (SOS-CRC-ds): 1</li> <li>e. DS Maximum Number of SOS (MAX-SOS-ds): 15</li> <li>f. DS SNRM offset for the ROC (SNRMOFFSET-ROC-ds): 6dB</li> <li>g. DS INPMIN for ROC (INPMIN-ROC-ds): 8 symbols</li> </ul> <p>NOTE - SOS triggering condition specified by parameter SOS-NTONES is superseded with the number of degraded tones <math>\geq 129</math> (Section 13.4.3.2/G.993.2 [6]).</p> <p>(4) Inject -140 dBm/Hz AWGN noise at both VTU-O and VTU-R.</p> <p>(5) Specific settings: SRA settings from Table 25.</p>
<b>Method of Procedure</b>	<p>(1) Connect the VTU-O and VTU-R. Wait for the modems to sync. NOTE - The SOS capability SHOULD be disabled in this phase.</p> <p>(2) Add the crosstalk noise defined in TR-114[2] for the band-profile under test at the VTU-R side only, and ensure the link breaks down before Downstream Minimum Downshift Rate Adaptation time. If not, deactivate the line and then enhance the noise power level by 1 dB per step and re-inject to the link, which is established under the noise of AWGN-140dBm/Hz only, at the VTU-R side. The Upper-limit of noise power level increase is 6dB above the initial noise level. Repeat the procedure above until the link breaks down once the noise is injected or the 6 dB noise increase limit is reached. Record the final noise value, as Noise_SOS-ds.</p> <p>(3) Force a new initialization.</p> <p>(4) Wait for 1 minute after initialization and record the downstream net data rate NDR_REINIT_DS. NOTE - this is the downstream data rate that would be obtained if the VTU were to (re-)initialize in the crosstalk noise condition using the same Transmit PSD level.</p> <p>(5) Deactivate the line.</p> <p>(6) Remove the crosstalk noise.</p> <p>(7) Enable SOS function by setting RA-MODE to 4 (DYNAMIC with SOS rate adaptation mode).</p> <p>(8) Force a new initialization.</p> <p>(9) Wait for 1 minute after initialization.</p> <p>(10) Inject the Noise_SOS-ds at the VTU-R side only.</p> <p>(11) Record the net data rate NDR_SOS_BEG_DS one second after the crosstalk is injected. NOTE - this is the downstream data rate in the crosstalk noise condition</p>

	<p>at the end of SOS procedure.</p> <p>(12) Record the data rate NDR_SOS_END_DS three minutes after the crosstalk is injected.</p> <p>NOTE - this is the downstream data rate in the crosstalk noise condition at the end of SRA procedure.</p>
<b>Expected Result</b>	<p>(1) No retrain SHALL occur during the test, after enabling SOS function.</p> <p>(2) NDR_SOS_BEG_DS &gt; MIN-SOS-BR-ds.</p> <p>(3) NDR_SOS_END_DS &gt; 0.8*NDR_REINIT_DS.</p>

**Table 35 - SOS Test in the Upstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) According to the band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see Section 4.2.3). If for the specific band-profile, profile-line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Configure the following settings:</p> <ul style="list-style-type: none"> <li>a. US Minimum SOS Bit Rate (MIN-SOS-BR-us): 5000kbps</li> <li>b. US SOS time Window (SOS-TIME-us): 64ms</li> <li>c. US Minimum Percentage of Degraded Tones (SOS-NTONES-us): 50</li> <li>d. US Minimum Number of normalized CRC anomalies (SOS-CRC-us): 1</li> <li>e. US Maximum Number of SOS (MAX-SOS-us): 15</li> <li>f. US SNRM offset for the ROC (SNRMOFFSET-ROC-us): 6dB</li> <li>g. US INPMIN for ROC (INPMIN-ROC-us): 8 symbols</li> </ul> <p>NOTE - SOS triggering condition specified by parameter SOS-NTONES is superseded with the number of degraded tones <math>\geq 129</math> (Section 13.4.3.2/G.993.2).</p> <p>(4) Set the noise generator to -140 dBm/Hz AWGN noise at both VTU-O and VTU-R.</p> <p>(5) Specific settings: SRA settings from Table 25.</p>
<b>Method of Procedure</b>	<p>(1) Connect the VTU-O and VTU-R. Wait for the modems to sync. NOTE - The SOS capability SHOULD be disabled in this phase.</p> <p>(2) Add the crosstalk noise defined in TR-114 for the band-profile under test at the VTU-O side only, and ensure the link breaks down before Upstream Minimum Downshift Rate Adaptation time. If not, deactivate the line, then enhance the noise power level by 1 dB per step and re-inject to the link, which is established under the noise of AWGN - 140dBm/Hz only, at VTU-O side. The Upper-limit of noise power level is 6dB above the initial noise level. Repeat the procedure above until the link breaks down once the noise is injected or the 6 dB noise increase limit is reached. Record the final noise value, as Noise_SOS-us.</p> <p>(3) Force a new initialization.</p> <p>(4) Wait for 1 minute after initialization and record the upstream net data rate NDR_REINIT_US. NOTE - this is the upstream data rate that would be obtained if the VTU were to (re-)initialize in the crosstalk noise condition using the same Transmit PSD level.</p> <p>(5) Deactivate the line.</p> <p>(6) Remove the crosstalk noise.</p> <p>(7) Enable SOS function by setting RA-MODE to 4 (DYNAMIC with SOS rate adaptation mode).</p> <p>(8) Force a new initialization.</p> <p>(9) Wait for 1 minute after initialization.</p> <p>(10) Inject the Noise_SOS-us at the VTU-O side only.</p> <p>(11) Record the net data rate NDR_SOS_BEG_US one second after the crosstalk is injected. NOTE - this is the upstream data rate in the crosstalk noise condition at</p>

	<p>the end of SOS procedure.</p> <p>(12) Record the data rate NDR_SOS_END_US three minutes after the crosstalk is injected.</p> <p>NOTE - this is the upstream data rate in the crosstalk noise condition at the end of SRA procedure.</p>
<b>Expected Result</b>	<p>(1) No retrain SHALL occur during the test, after enabling SOS function.</p> <p>(2) NDR_SOS_BEG_US &gt; MIN-SOS-BR-us</p> <p>(3) NDR_SOS_END_US &gt; 0.8*NDR_REINIT_US</p>

#### 5.4.6 Bitswap to Zero-Bit-Loading Test

This test injects noise (a single frequency sine wave) on a specific tone and verifies that bit swap functions lower the bit loading on the affected tone to zero bits as the injected noise is increased.

**Table 36 - Bitswap to zero bit loading test**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) Configure the SUT according to the settings of the rate adaptive (RA) profile-line combination under test defined in regional annexes (A and B).</p> <p>(3) Connect VTU-O and VTU-R to</p> <ol style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ol> <p>(4) All single frequency tone amplitudes that are applied are referenced in terms of power levels (dBm) at the injection point on the loop, calibrated with the VTU-O and VTU-R replaced with calibrated 100 Ohm <math>\pm</math> 1% resistors. Measurements SHALL be performed into a 1kHz resolution bandwidth. Note that with a 1kHz resolution bandwidth the power spectral density value (in dBm/Hz) will be 30dB less than the power level (in dBm), limited by the noise floor of the test equipment used for calibration. The frequency of the interfering tone SHALL be set to <math>n \times 4.3125</math> kHz for profiles up to 17MHz or <math>n \times 8.625</math> kHz for 30MHz profile. The power of the interfering tone SHALL be -75 dBm.</p> <p>(5) Set the noise generator to -140dBm/Hz AWGN noise at both VTU-O and VTU-R.</p>
<b>Method of Procedure</b>	<p>(1) Force initialization and wait for the modems to sync.</p> <p>(2) Wait for 1 minute after initialization.</p> <p>(3) Record the bit allocation tables (BITSpsus and BITSpsds) and the actual net data rates (ACTNDRus and ACTNDRds).</p> <p>(4) Randomly select an integer value, n, the tone number in</p> <ol style="list-style-type: none"> <li>a. the upstream passband range for the upstream test and</li> <li>b. the downstream passband range for the downstream test, applicable to the chosen band-profile.</li> </ol> <p>Avoid the use of the pilot tone or any unpopulated tones. Ensure that the tone selected has assigned bits as described in the relevant bits per tone map, also after the injection of the RFI in MOP(7).</p> <p>(5) Record and report the value of n used.</p>

	<p>(6) Reprovision the line with the maximum upstream and downstream data rates in the profile set to 90% of the actual data rates recorded in MOP(3).</p> <p>(7) Inject the interfering tone at the:</p> <ol style="list-style-type: none"> <li>a. VTU-O for the upstream test</li> <li>b. VTU-R for the downstream test</li> </ol> <p>(8) Train the link and wait 1 minute after initialization.</p> <p>(9) Record the number of bits for the selected interfering tone. If the number of bits is zero then select (and report the value of) another tone in the related passband and reconfigure the signal generator frequency accordingly. Repeat MOP(7) to MOP(9) until a non-zero bit loading is found.</p> <p>(10) Increase the power of the interfering tone by 5 dBm .</p> <p>(11) Wait 30 seconds and record the number of bits assigned to the tone. Repeat MOP(10) and MOP(11) until the tone has no bits loaded.</p> <p>(12) Remove the interfering tone at the VTU-O side.</p> <p>(13) Repeat MOP(7) to MOP(12) for the downstream test.</p>
<b>Expected Result</b>	<p>(1) The modem SHALL NOT lose sync.</p> <p>(2) The number of bits assigned to the affected tone before MOP(12) SHALL equal zero.</p>

### 5.5 Loop Diagnostic Mode Test

The purpose of this test is to verify the functionality of the Loop Diagnostic mode. Loop Diagnostic mode is intended to identify channel conditions at both ends of the loop without transitioning to the L0 state. The modems SHALL return to L3 state after completion of the Loop Diagnostic mode. Test parameters exchanged during the Loop Diagnostic mode are defined in Section 11.4.1/G.993.2 and Section 7.5.1/G.997.1.

**Table 37 - Test on Loop Diagnostic Mode requested by VTU-O**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT with one of the profile-line combinations associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Specific settings to force the VTU to perform the LD mode: set the line configuration parameter LDSF to 1.</p> <p>(4) Connect VTU-O and VTU-R to:</p> <ol style="list-style-type: none"> <li>a. 1350 ft 26AWG for profiles up to 17MHz or 450 ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> <li>or</li> <li>c. 450m TP100 for profiles up to 17MHz or 150m TP100 for 30MHz profiles</li> </ol> <p>(5) Inject -120 dBm/Hz AWGN noise at both the VTU-O and VTU-R ends.</p>
<b>Method of</b>	(1) Force the line at the VTU-O side to the L3 state.

<b>Procedure</b>	<ul style="list-style-type: none"> <li>(2) Force the VTU-O to perform the loop diagnostic mode.</li> <li>(3) Collect and record the following “per band” test parameters: LATN, SATN, SNRM, in both downstream and upstream.</li> <li>(4) Collect and record the following test parameters: ATTNDR and ACTATP, in both downstream and upstream.</li> <li>(5) Collect and record the following parameters for the linear channel characteristics function per subcarrier group: HLINSC, HLING, HLINps, in both downstream and upstream.</li> <li>(6) Collect and record the following parameters for the logarithmic channel characteristics function per subcarrier group: HLOGMT, HLOGG, HLOGps, in both downstream and upstream.</li> <li>(7) Collect and record the following parameters for the Quiet line noise PSD per subcarrier group: QLNMT, QLNG, QLNps, in both downstream and upstream.</li> <li>(8) Collect and record the following parameters for the Signal-to-noise ratio per subcarrier group: SNRMT, SNRG, SNRps in both downstream and upstream.</li> </ul>
<b>Expected Result</b>	<p>After successful completion of the Loop Diagnostic mode:</p> <ul style="list-style-type: none"> <li>(1) The line returns to the L3 state</li> <li>(2) Line configuration parameter LDSF set to 0</li> <li>(3) The requirements for the line diagnostic parameters: Loop attenuation per band (LATN), Signal attenuation per band (SATN) and Signal-to-noise ratio margin per band (SNRM) apply within the specified ranges as specified in Section 7.5.1.9/10, 7.5.1.11/12 and 7.5.1.14/17 of G.997.1.</li> <li>(4) The requirements for the line diagnostic parameters: Attainable net data rate (ATTNDR) and Actual aggregate transmit power (ACTATP) apply within the specified ranges as specified in Section 7.5.1.19/20 and 7.5.1.24/25 of G.997.1.</li> <li>(5) The requirements for the linear channel characteristics function per subcarrier group: representation scale (HLINSC), group size (HLING) and an array of complex values in linear scale for Hlin(f) (HLINps) apply within the specified ranges as specified in Section 7.5.1.26.1-3 and 7.5.1.26.7-9 of G.997.1.</li> <li>(6) The requirements for the logarithmic channel characteristics function per subcarrier group: measurement time (HLOGMT), group size (HLOGG) and an array of real values in dB for Hlog(f) (HLOGps) apply within the specified ranges as specified in Section 7.5.1.26.4-6 and 7.5.1.26.10-12 of G.997.1.</li> <li>(7) The requirements for the Quiet line noise PSD per subcarrier group: measurement time (QLNMT), group size (QLNG) and an array of real values in dBm/Hz for QLN(f) (QLNps) apply within the specified ranges as specified in Section 7.5.1.27.1-3 and 7.5.1.27.4-6 of G.997.1.</li> <li>(8) The requirements for the Signal-to-noise ratio per subcarrier group: measurement time (SNRMT), group size (SNRG) and an array of real values in dB for SNR(f) (SNRps) apply within the specified ranges as specified in Section 7.5.1.28.1-3 and 7.5.1.28.4-6 of G.997.1.</li> </ul>



**Table 38 - Test on Loop Diagnostic Mode requested by VTU-R**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for test configuration.</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT with one of the profile-line combinations associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(3) Specific settings to force the VTU to perform the LD mode: set the line configuration parameter LDSF to 1.</p> <p>(4) Connect VTU-O and VTU-R to:</p> <ul style="list-style-type: none"> <li>a. 1350 ft 26AWG for profiles up to 17MHz or 450 ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450 m PE 0.4mm for profiles up to 17MHz or 150 m PE 0.4mm for 30MHz profiles</li> <li>or</li> <li>c. 450m TP100 for profiles up to 17MHz or 150m TP100 for 30MHz profiles</li> </ul> <p>(5) Inject -120 dBm/Hz AWGN noise at both the VTU-O and VTU-R ends.</p>
<b>Method of Procedure</b>	<p>(1) Force the line at the VTU-R side to the L3 state.</p> <p>(2) Force the VTU-R to perform the loop diagnostic mode.</p> <p>(3) Collect and record the following “per band” test parameters: LATN, SATN, SNRM, in both downstream and upstream.</p> <p>(4) Collect and record the following test parameters: ATTNDR and ACTATP, in both downstream and upstream.</p> <p>(5) Collect and record the following parameters for the linear channel characteristics function per subcarrier group: HLINSC, HLING, HLINps, in both downstream and upstream.</p> <p>(6) Collect and record the following parameters for the logarithmic channel characteristics function per subcarrier group: HLOGMT, HLOGG, HLOGps, in both downstream and upstream.</p> <p>(7) Collect and record the following parameters for the Quiet line noise PSD per subcarrier group: QLNMT, QLNG, QLNps, in both downstream and upstream.</p> <p>(8) Collect and record the following parameters for the Signal-to-noise ratio per subcarrier group: SNRMT, SNRG, SNRps in both downstream and upstream.</p>
<b>Expected Result</b>	<p>After successful completion of the Loop Diagnostic mode:</p> <p>(1) The line returns to remain in the L3 state.</p> <p>(2) Line configuration parameter LDSF set to 0.</p> <p>(3) The requirements for the line diagnostic parameters: Loop attenuation per band (LATN), Signal attenuation per band (SATN) and Signal-to-noise ratio margin per band (SNRM) apply within the specified ranges as specified in Section 7.5.1.9/10, 7.5.1.11/12 and 7.5.1.14/17 of G.997.1.</p> <p>(4) The requirements for the line diagnostic parameters: Attainable net data rate (ATTNDR) and Actual aggregate transmit power (ACTATP) apply within the specified ranges as specified in Section 7.5.1.19/20</p>

	<p>and 7.5.1.24/25 of G.997.1.</p> <p>(5) The requirements for the linear channel characteristics function per subcarrier group: representation scale (HLINSC), group size (HLING) and an array of complex values in linear scale for Hlin(f) (HLINps) apply within the specified ranges as specified in Section 7.5.1.26.1-3 and 7.5.1.26.7-9 of G.997.1.</p> <p>(6) The requirements for the logarithmic channel characteristics function per subcarrier group: measurement time (HLOGMT), group size (HLOGG) and an array of real values in dB for Hlog(f) (HLOGps) apply within the specified ranges as specified in Section 7.5.1.26.4-6 and 7.5.1.26.10-12 of G.997.1.</p> <p>(7) The requirements for the Quiet line noise PSD per subcarrier group: measurement time (QLNMT), group size (QLNG) and an array of real values in dBm/Hz for QLN(f) (QLNps) apply within the specified ranges as specified in Section 7.5.1.27.1-3 and 7.5.1.27.4-6 of G.997.1.</p> <p>(8) The requirements for the Signal-to-noise ratio per subcarrier group: measurement time (SNRMT), group size (SNRG) and an array of real values in dB for SNR(f) (SNRps) apply within the specified ranges as specified in Section 7.5.1.28.1-3 and 7.5.1.28.4-6 of G.997.1.</p>
--	---

## 5.6 VTU-R Inventory Test

The purpose of this test is to verify that the VTU-R inventory formatting is correct according to Section 7.4/G.997.1 and the information contained within the fields is consistent with the equipment identification information provided by the equipment supplier to the test lab.

**Table 39 - VTU-R Inventory Information Test**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p>
<b>Method of Procedure</b>	<p>(1) Force a new initialization and wait for VTU-R to sync.</p> <p>(2) Wait for 1 minute after initialization for EoC data to be exchanged.</p>
<b>Expected Results</b>	<p>(1) VTU-R Vendor ID is correct as specified in Section 7.4.2/G.997.1</p> <ol style="list-style-type: none"> <li>a. The T.35 country code (2 octets) is correct for the country of the vendor of the VTU-R VDSL2 Chipset.</li> <li>b. The T.35 provider code (vendor identification) (4 octets) correctly identifies the vendor of the VDSL2 Chipset.</li> </ol> <p>(2) VTU-R System Vendor ID is correct as specified in Section 7.4.4/G.997.1</p> <ol style="list-style-type: none"> <li>a. The T.35 country code (2 octets) is correct for the country of the system integrator (VTU-R vendor).</li> <li>b. The T.35 provider code (vendor identification) (4 octets) correctly identifies VTU-R vendor (NOTE).</li> </ol> <p>(3) VTU-R version number is correct as specified in Section 7.4.6/G.997.1</p> <ol style="list-style-type: none"> <li>a. It contains the VTU-R firmware version and the VTU-R model. Both SHALL be encoded in this order and separated by a space character, i.e. "&lt;VTU-R firmware version&gt; &lt;VTU-R model&gt;".</li> </ol>

	<p>(4) VTU-R serial number is correct as specified in Section 7.4.8/G.997.1</p> <p>a. It contains the equipment serial number, the equipment model and the equipment firmware version. All SHALL be encoded in this order and separated by space characters, i.e. "&lt;equipment serial number&gt; &lt;equipment model&gt; &lt;equipment firmware version&gt;".</p>
NOTE - System Vendor ID MAY be different from the Vendor ID.	

## 5.7 PSD Tests

### 5.7.1 PSD Test

The purpose of this test is to verify that the PSD of signals transmitted by a VTU during Showtime complies with the requirements defined in G.993.2 [6].

NOTE - this test is conceived for profile-line combinations with PBO disabled.

Measurements SHALL include both the passband and stopband frequencies.

**Table 40 - PSD Test**

<b>Test Configuration</b>	<p>(1) The VTU modems SHALL be connected as shown in Section 4.1.</p> <p>(2) The test setup SHALL support the PSD mask measurement over the entire downstream and upstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz.</p> <p>(3) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3).</p> <p>(4) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex, Section 4.4. Its length SHALL be varied in:</p> <ul style="list-style-type: none"> <li>- 5 steps from the NULL loop to the length at which the loop is the equivalent of 20dB @ 1MHz for profiles up to 17MHz.</li> <li>- 3 steps from the NULL loop to the length at which the loop is the equivalent of 6dB @ 1MHz for profiles up to 30MHz.</li> </ul> <p>Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz.</p>
---------------------------	---

<b>Method of Procedure</b>	<p>(1) Force initialization and wait for modems to synchronize.</p> <p>(2) Wait 1 minute following synchronization.</p> <p>(3) Record the gain allocation tables (GAINSpS) and MEDLEY reference PSD (MREFPSD) for direction under test.</p> <p>(4) Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the PSD to be measured (NOTE 1).</p> <p>(5) PSD SHALL be measured in one of the following ways:</p> <ol style="list-style-type: none"> <li>over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>over a wideband 50:100 BALUN transformer (assumes 50ohm analyser)</li> </ol> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the PSD measurement.</p> <p>(6) Record the measured transmit PSD (TXPSD) data for direction under test.</p> <p>(7) Calculate the smoothed PSD (STXREFPSD) by averaging the measured transmit PSD without the GAINSpS (TXREFPSD) over a 48kHz window (NOTE 2) centered on the subcarrier frequency SC:</p> $STXREFPSD(SC) = 10 \times \log_{10} \left( \left( \frac{1}{11} \right) \times \sum_{i=-5}^5 10^{\frac{TXREFPSD(SC+i)}{10}} \right), \text{ for}$ <p><math>SC_{\text{band\_start}} + 5 \leq SC \leq SC_{\text{band\_end}} - 5</math>, where <math>band \in \{ds\_bands\}</math> or <math>band \in \{us\_bands\}</math>.</p> <p>(8) Repeat MOP(1) through MOP(7) for all loop lengths (between NULL loop and the defined maximum loop) according to test configuration TC(4).</p> <p>NOTE 1- If the VTUs cannot operate in the mode described in MOP(4), the test setup SHALL provide adequate isolation of the downstream and upstream transmit signals between the two transceivers to allow for an accurate measurement to be made, while both transceivers remain connected and in state L0. If mode described in MOP(4) is unavailable, the measurements will not be made on loops or attenuation settings not providing adequate isolation, and the measurement method used will be noted within the test report.</p> <p>NOTE 2 - 96 kHz for 30MHz profiles.</p>
<b>Expected Result</b>	<p>(1) Measured PSD TXPSD SHALL be <math>\leq</math> LIMITMASK.</p> <p>(2) Calculated STXREFPSD SHALL be <math>\leq</math> LIMITMASK -2.0 dB (NOTE 3).</p> <p>(3) Measured aggregate transmit power SHALL be <math>\leq</math> MAXNOMATP and the maximum aggregate downstream/upstream transmit power specified in Table 6-1/G.993.2 [6].</p> <p>NOTE 3 - Includes 0.5dB for test equipment tolerance.</p>

### 5.7.2 Aggregate Transmit Power Test

The purpose of this test is to verify that the VTU-O and VTU-R does not transmit the total amount of transmit power that exceeds the maximum downstream/upstream transmit power specified in

G.993.2 for each VDSL2 profile. The aggregate transmit power SHALL be measured over the entire passband and stopband frequencies.

NOTE - this test is conceived for profile-line combinations with PBO disabled.

**Table 41 - Aggregate Transmit Power Test**

<b>Test Configuration</b>	<p>(1) The VTU modems SHALL be connected as shown in Section 4.1</p> <p>(2) The test setup SHALL support the aggregate transmit power (ATP) measurement over the entire downstream and upstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz.</p> <p>(3) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3).</p> <p>(4) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex Section 4.4. Its length SHALL be varied in:</p> <ul style="list-style-type: none"> <li>- 5 steps from the NULL loop to the length at which the loop is the equivalent of 20dB @ 1MHz for profiles up to 17MHz.</li> <li>- 3 steps from the NULL loop to the length at which the loop is the equivalent of 6dB @ 1MHz for profiles up to 30MHz.</li> </ul> <p>Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz</p>
<b>Method of Procedure</b>	<p>(1) Connect and configure the VTU-O and VTU-R as per test configuration details.</p> <p>(2) Force initialization and wait for modems to synchronize.</p> <p>(3) Wait 1 minute following synchronization. Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the ATP to be measured (NOTE).</p> <p>(4) ATP SHALL be measured in one of the following ways:</p> <ul style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyser)</li> </ul> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the power measurement.</p> <p>(5) Take a note of the measured downstream and upstream aggregate transmit power.</p> <p>(6) Repeat MOP(2) through MOP(5) for all five loop lengths (between NULL loop and the defined maximum loop) according to the test configuration TC(5).</p>
<b>Expected Result</b>	<p>(1) Measured aggregate transmit power SHALL be <math>\leq</math> the maximum aggregate downstream/upstream transmit power specified in Table 6-1/G.993.2 [6].</p>

NOTE - If the VTUs cannot operate in the mode described in MOP(3), the test setup SHALL provide adequate isolation of the downstream and upstream transmit signals between the two transceivers to allow for an accurate measurement to be made, while both transceivers remain connected and in state L0. If mode described in MOP(4) is unavailable, the measurements will not be made on loops or attenuation settings not providing adequate isolation, and the measurement method used will be noted within the test report.

### 5.7.3 In-band Spectral Shaping Test

The purpose of this test is to verify the ability of VDSL2 transmitters to reduce the PSD of the transmitted signal to a level below -80dBm/Hz in 16 arbitrary frequency bands simultaneously. An example list of frequency bands is shown in Table 42. The data is sourced from ITU-T G.993.2 and T-Systems. First two RFI notches are in line with the specification from TR-100 (section A.1 and B.3.7).

**Table 42 - List of some predefined RFI Notches**  
(source: Europe/Germany, incl. international amateur radio bands)

Frequency	Application
1,800 – 2,000 MHz	amateur radio
2,173 – 2,191 MHz	GMDSS (Global Maritime Distress and Safety Service)
2,850 – 3,155 MHz	aeronautical communications
3,400 – 3,500 MHz	aeronautical communications
3,500 – 3,800 MHz	amateur radio
3,800 – 4,000 MHz	aeronautical communications / broadcasting
3,500 – 4,000 MHz	amateur radio
4,200 – 4,215 MHz	GMDSS
4,650 – 4,850 MHz	aeronautical communications
5,450 – 5,730 MHz	aeronautical communications
5,900 – 6,200 MHz	(future) DRM radio (broadcasting)
6,300 – 6,320 MHz	GMDSS
6,525 – 6,765 MHz	aeronautical communications
7,000 – 7,300 MHz	amateur radio
7,000 – 7,200 MHz	amateur radio
7,200 – 7,450 MHz	(future) DRM radio (broadcasting)
8,405 – 8,420 MHz	GMDSS
8,815 – 9,040 MHz	aeronautical communications
9,400 – 9,900 MHz	(future) DRM radio
10,005 – 10,100 MHz	aeronautical communications
10,100 – 10,150 MHz	amateur radio
11,175 – 11,400 MHz	aeronautical communications
11,600 – 12,100 MHz	(future) DRM radio (Broadcasting)
12,570 – 12,585 MHz	GMDSS
13,200 – 13,360 MHz	aeronautical communications
13,570 – 13,870 MHz	(future) DRM radio (Broadcasting)
14,000 – 14,350 MHz	amateur radio
15,010 – 15,100 MHz	aeronautical communications
15,100 – 15,800 MHz	(future) DRM radio (broadcasting)
16,795 – 16,810 MHz	GMDSS
17,480 – 17,900 MHz	(future) DRM radio (broadcasting)

Frequency	Application
17,900 – 18,030 MHz	aeronautical communications
18,068 – 18,168 MHz	amateur radio
21,000 – 21,450 MHz	amateur radio
24,890 – 24,990 MHz	amateur radio
26,965 – 27,405 MHz	CB radio
28,000 – 29,700 MHz	amateur radio

**Table 43 - In-band Spectral Shaping / RFI Notch Configuration Test**

<b>Test Configuration</b>	<p>(1) The VTU modems SHALL be connected as shown in Section 4.1.</p> <p>(2) The test setup SHALL support the PSD mask and aggregate transmit power (ATP) measurements over the entire downstream and upstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz.</p> <p>(3) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p>(4) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex, Section 4.4. Its length SHALL be set to the length at which the loop is the equivalent of:</p> <ul style="list-style-type: none"> <li>- 20dB @ 1MHz for profiles up to 17MHz.</li> <li>- 6dB @ 1MHz for profiles up to 30MHz.</li> </ul> <p>Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz.</p>
<b>Method of Procedure</b>	<p>(1) Set spectrum analyzer for the requested frequency range, resolution bandwidth and input attenuation range to prevent it from being overridden.</p> <p>(2) Configure 16 different RFI bands. A list of possible configuration is shown in Table 42.</p> <p>(3) Force initialization and wait for modems to synchronize.</p> <p>(4) Wait 1 minute following synchronization.</p> <p>(5) Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the PSD to be measured (NOTE).</p> <p>(6) PSD SHALL be measured, while ATP could be measured or calculated from the PSD. in one of the following ways:</p> <ul style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe.</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50 ohm analyser).</li> </ul> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the measurement.</p> <p>(7) Take a note of the measured downstream and upstream PSD data.</p> <p>(8) Take a note of the measured or calculated downstream and upstream ATP.</p>

<b>Expected Result</b>	(1) Measured PSD mask SHALL comply with the requirements from Section 7.2.3/G.993.2 [6]. (2) Measured PSD mask SHALL be $\leq$ the Limit PSD mask (LIMITMASK).
NOTE - If the VTUs cannot operate in the mode described in MOP(5), the test setup SHALL provide adequate isolation of the downstream and upstream transmit signals between the two transceivers to allow for an accurate measurement to be made, while both transceivers remain connected and in state L0. If mode described in MOP(4) is unavailable, the measurements will not be made on loops or attenuation settings not providing adequate isolation, and the measurement method used will be noted within the test report.	

**5.7.4 Downstream Power Back-off Test**

The purpose of this test is to verify the modified VTU-O transmit PSD mask based on the downstream power back-off configuration parameters and procedure described in Section 7.3.1.2.13/G.997.1.

**Table 44 - Downstream Power Back-Off Test**

<b>Test Configuration</b>	(1) The VTU modems SHALL be connected as shown in Section 4.1 (2) The test setup SHALL support the PSD mask and optionally aggregate transmit power (ATP) measurements, over the entire downstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz. (3) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with UPBO enabled, apply the related UPBO configuration parameters. If, for the specific band-profile, profile-line combinations are defined with DPBO enabled, apply the related DPBO configuration parameters. Otherwise define one set of DPBO parameters (DPBOEPSD, DPBOESCMA, -B, -C, DPBOMUS, DPBOFMIN, DPBOFMAX). (4) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex Section 4.4. Its length SHALL be set to the length at which the loop is the equivalent of: - 20dB @ 1MHz for profiles up to 17MHz. - 6dB @ 1MHz for profiles up to 30MHz Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz. (5) Set DPBOESEL to 10 dB.
---------------------------	--



<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Set spectrum analyzer for the requested frequency range, resolution bandwidth and input attenuation range to prevent it from being overdriven.</li> <li>(2) Force initialization and wait for modems to synchronize.</li> <li>(3) Wait 1 minute following synchronization.</li> <li>(4) Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the PSD to be measured (NOTE).</li> <li>(5) PSD SHALL be measured, while ATP could be measured or calculated from the PSD. in one of the following ways: <ol style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyser)</li> </ol> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the measurement.</p> </li> <li>(6) Record the measured PSD data.</li> <li>(7) Optionally record the measured or calculated ATP.</li> <li>(8) Repeat MOP(2) through MOP(7) for the following DPBOESEL values: 20dB, 30dB, 40dB, 50dB and 60dB.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) VTU-O and VTU-R SHALL synchronize in all tested configurations.</li> <li>(2) Measured PSD mask SHALL comply with the requirements from Section 7.3.1.2.13/G.997.1</li> <li>(3) Measured PSD mask SHALL be <math>\leq</math> the resultant mask (RESULTMASK ds).</li> </ol>
<p>NOTE - If the VTUs cannot operate in the mode described in MOP(4), the test setup SHALL provide adequate isolation of the downstream and upstream transmit signals between the two transceivers to allow for an accurate measurement to be made, while both transceivers remain connected and in state L0. If mode described in MOP(4) is unavailable, the measurements will not be made on loops or attenuation settings not providing adequate isolation, and the measurement method used will be noted within the test report.</p>	

### 5.7.5 Upstream Power Back-off Test

The purpose of this test is to verify that the upstream power back-off (UPBO) mechanism in the VTU-R is implemented correctly according to the directions of section 7.2.1.3/G.993.2 and that the VTU-R transmit signal in Showtime is adapted to conform to the upstream power back-off mask  $UPBOMASK(kl_0, f)$  while remaining below the transmit PSD mask limit communicated to the VTU-R at the beginning of initialization and within the limit imposed by the upstream PSD ceiling. One set of configuration parameters (a,b) for the UPBO reference PSD SHALL be defined for each upstream band in the selected VDSL2 band-profile, except the US0.

**Table 45 - Upstream Power Back-Off Test**

<b>Test Configuration</b>	<p>(1) The VTU modems SHALL be connected as shown in Section 4.1</p> <p>(2) The test setup SHALL support the PSD mask and optionally aggregate transmit power (ATP) measurements, over the entire upstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz.</p> <p>(3) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO enabled, apply the related DPBO configuration parameters. If, for the specific band-profile, profile-line combinations are defined with UPBO enabled, apply the related UPBO configuration parameters. Otherwise define one set of UPBO parameters (a, b) for each upstream band.</p> <p>(4) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex, as referenced in Section 4.4. Its length SHALL be set to the length at which the loop is the equivalent of:</p> <ul style="list-style-type: none"> <li>a. 0dB @ 1MHz;</li> <li>b. 10dB @ 1MHz;</li> <li>c. 20dB @ 1MHz</li> </ul> <p>Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz.</p>
---------------------------	--

<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Set spectrum analyzer for the requested frequency range, resolution bandwidth and input attenuation range to prevent it from being overdriven.</li> <li>(2) Force initialization and wait for modems to synchronize.</li> <li>(3) Wait 1 minute following synchronization.</li> <li>(4) Record the estimated electrical length <math>kl_0</math> (UPBOKLE).</li> <li>(5) Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the PSD to be measured (NOTE).</li> <li>(6) PSD SHALL be measured, while ATP could be measured or calculated from the PSD, in one of the following ways: <ol style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyser)</li> </ol> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the measurement.</p> </li> <li>(7) Record the measured PSD data.</li> <li>(8) Optionally record the measured or calculated ATP.</li> <li>(9) Repeat MOP(2) through MOP(8) for all three loop lengths (between NULL loop and the defined maximum loop) according to the test configuration TC(5).</li> <li>(10) Deactivate the line.</li> <li>(11) Maintain the test loop equivalent to 20 dB @ 1MHz.</li> <li>(12) Configure the parameter UPBOKLF to 1 to force the VTU-R to use the electrical length <math>kl_0</math> configured by the CO-MIB (UPBOKL) to compute the UPBO. Set the <math>kl_0</math> value UPBOKL to 15dB and repeat MOP(2) through MOP(8).</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) VTU-O and VTU-R SHALL synchronize in all tested configurations.</li> <li>(2) Measured PSD mask SHALL comply with the requirements from Section 7.2.1.3.2/G.993.2 [6].</li> <li>(3) Measured PSD mask SHALL be <math>\leq</math> the reference UPBO mask (UPBOMASK(<math>kl_0</math>, f)) calculated with <math>kl_0</math> value=1.8 for 0dB loop, or estimated <math>kl_0</math> value for non-0dB loop, or with UPBOKL for the case with forced <math>kl_0</math>.</li> </ol>
<p>NOTE - If the VTUs cannot operate in the mode described in MOP(5), the test setup SHALL provide adequate isolation of the downstream and upstream transmit signals between the two transceivers to allow for an accurate measurement to be made, while both transceivers remain connected and in state L0. If mode described in MOP(4) is unavailable, the measurements will not be made on loops or attenuation settings not providing adequate isolation, and the measurement method used will be noted within the test report.</p>	

## 5.8 Longitudinal Conversion Loss (LCL) Test

The purpose of this test is to verify the longitudinal conversion loss (LCL) of the VDSL2 transceiver fulfills the requirement from section 7.4 in G.992.3. LCL is a measure in dB of the

degree of unwanted transversal signal produced at the input of the VDSL2 transceiver ( $V_{diff}$ ) due to the presence of a longitudinal signal ( $V_{cm}$ ) on the connecting leads:  $LCL=20 \log |V_{cm}/V_{diff}|$ .

**Table 46 - Longitudinal Conversion Loss (LCL) Test**

<b>Test Configuration</b>	(1) See Section 4.1 for the test configuration. (2) As per VDSL2 band-profile to be tested, configure the SUT in one of the profile line combinations associated to that band-profile (see Section 4.2.3). (3) During the test, the transceiver under test SHALL be powered in L3 state and not transmitting any signal.
<b>Method of Procedure</b>	(1) Measure the LCL as specified in G.117 [3] and O.9 [10].
<b>Expected Result</b>	(1) $LCL \geq 38$ dB in the frequency band up to 12 MHz. (2) $LCL \geq 38$ dB – $20 \log_{10}(f_{[MHz]}/12)$ for $12 \text{ MHz} < f < F_{max}$ .

## 5.9 VTU-R INM

The purpose of this test is to verify that the impulse noise monitoring (INM) function and associated control and configuration INM parameters are implemented correctly according to the directions of the G.993.2 (clauses 11.2.3.13, 11.3.4.3, 11.4.2.2) and G.997.1 standard (clauses 7.2.1.5, 7.3.1.9).

The INPEQ histogram corresponds to the calculated equivalent INP, and it is defined as integer number of DMT symbols between 1 and 16. A special value of 17 represents the equivalent INP of more than 16 DMT symbols. The IAT histogram is generated for several ranges of the inter-arrival time, which is representing a number of data symbols between the start of two neighboring clusters.

INMIATO and INMIATS define the INM inter-arrival time offset and time step for generation of the IAT histogram, while parameter INMCC is used in the noise bursts indication process. Finally, configuration parameter INPEQ\_MODE defines the way of computation of equivalent INP.

INM configuration parameters are defined in Table 47 and they apply to the downstream direction.

The symbol counts are only applicable for symbols using a CE length corresponding to  $m = 5$  (See §10.4.4 G.993.2 [6]) resulting in a symbol duration of 250  $\mu$ s (4 ksymbols/s) or 125  $\mu$ s (8 ksymbols/s).

NOTE - Tests with the parameter INM\_INPEQ\_MODE set to 1 are optional.

**Table 47 - VTU-R INM Tests**

Test	INM_INPEQ_MODE	INMIATO	INMIATS	INMCC	PEIN Test Sequence (See section 5.10.9)
1	0	3 (default)	0(default)	0	#1
2	0	3 (default)	0(default)	0	#2
3	0	3	2	0	#3
4	0	3	2	0	#4
5	0	27	4	0	#5
6	0	27	4	0	#6
7	0	123	6	0	#7
8	0	123	6	0	#8
9	0	511	7	0	#9
10	0	511	7	0	#10

<b>11</b>	1	3	2	2	#11
<b>12</b>	1	27	4	64	#12

**Table 48 - VTU-R INM Capability**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT in one of the profile line combinations associated to that band-profile in the rate adaptive mode (see Section 4.2.3).</p> <p>(3) The INM control parameters and PEIN test sequence for each test are defined in Table 47.</p> <p>(4) Connect VTU-R and VTU-O to:</p> <ol style="list-style-type: none"> <li>a. 1350 ft 26AWG (profiles up to 17MHz) or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450 m PE 0.4mm (profiles up to 17MHz) or 150 m PE 0.4mm for 30MHz profiles</li> </ol> <p>(5) Inject <math>-130\text{dBm/Hz}</math> AWGN noise at both the VTU-O and VTU-R ends</p> <p>(6) Additional test conditions:</p> <ul style="list-style-type: none"> <li>• The PEIN impulses SHALL be injected at the VTU-R end.</li> <li>• The interval borders of the INM counters SHALL be considered</li> </ul>
<b>Method of Procedure</b>	<p>(1) Power-cycle VTU-R.</p> <p>(2) Deactivate the line and configure the VTU-O as per Test 1/Table 47.</p> <p>(3) Activate the line and wait 1 minute following synchronization.</p> <p>(4) Force performance counters update and wait 30 seconds. Record the values of the INMINPEQ<sub>1..17-LFE</sub>, INMME-LFE and INMIAT<sub>0..7-LFE</sub> counters at the VTU-O side.</p> <p>(5) Inject PEIN Test sequence #1.</p> <p>(6) Force performance counters update and wait 30 seconds. Record values of INMINPEQ<sub>1..17-LFE</sub>, INMME-LFE and INMIAT<sub>0..7-LFE</sub> counters at the VTU-O side.</p> <p>(7) For test sequence #1 only force initialization without powering down the VTU-R and wait for modems to synchronize.</p> <p>(8) For test sequence #1 only record values of INMINPEQ<sub>1..17-LFE</sub>, INMME-LFE and INMIAT<sub>0..7-LFE</sub> counters at the VTU-O side.</p> <p>(9) Repeat MOP(2) through MOP(6) for the next test sequence as defined per Table 47.</p>

<b>Expected Result</b>	<p>(1) No loss of synchronization SHALL occur during the application of the test impulses.</p> <p>(2) For Test sequence#3, the initial histograms INMINPEQ<sub>1..17</sub>-LFE and INMIAT<sub>0..7</sub>-LFE SHALL contain <math>\leq 2</math> events. The INMME-LFE counter SHALL be <math>&gt; 200000</math> and <math>&lt; 400000</math> for profiles up to 17MHz, and SHALL be <math>&gt; 400000</math> and <math>&lt; 800000</math> for 30MHz profiles.</p> <p>(3) The increase of the INMME-LFE counter between MOP(4) and MOP(6) SHALL be in the range of the expected result in Sections 5.9.1 to 5.9.7 for each test.</p> <p>(4) The increase of the event count in the INMINPEQ<sub>1..17</sub>-LFE histogram between MOP(4) and MOP(6) SHALL be equal to the expected result in Sections 5.9.1 to 5.9.7 for each test. A tolerance of +1/-0 on one of the bins SHALL be permitted to allow for unexpected impulse events occurring in the test environment during the test sequence.</p> <p>(5) The increase of the event count in the INMIAT<sub>0..7</sub>-LFE histogram between MOP(4) and MOP(6) for each test SHALL equal to the expected result defined in Sections 5.9.1 to 5.9.7. A tolerance of +1/-0 on one of the bins SHALL be permitted to allow for unexpected impulse events occurring in the test environment during the test.</p> <p>(7) For Test sequence#1, the recorded values of INMIAT<sub>0..7</sub>-LFE and INMINPEQ<sub>1..17</sub>-LFE in MOP(8) SHALL be equal to the values recorded in MOP(6). A tolerance of +1/-0 on one of the bins SHALL be permitted to allow for unexpected impulse events occurring in the test environment during this step. The INMME-LFE count SHALL be <math>\geq</math> INMME-LFE count recorded in MOP(6).</p>
------------------------	---

### 5.9.1 Expected Results for Test 1

INMME (17MHz Profiles): [482000 ....761000]

INMME (30MHz Profiles): [964000...1523000]

#### INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	25		25			0	25			0	25		0	0	25		

#### INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	0	0	0	0	0	0	0	125

### 5.9.2 Expected Results for Test 2

INMME (17MHz Profiles): [462000... 741000]

INMME (30MHz Profiles): [924000...1483000]

## INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	0	30			0	30			0	30			0	30			0

## INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	0	0	0	0	0	0	0	120

**5.9.3 Expected Results for Test 3**

INMME (17MHz Profiles): [462000... 741000]

INMME (30MHz Profiles): [924000...1483000]

## INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	240-2*q			q (q<=30)			0	0	0	0	0	0	0	0	0	0	0

## INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	30-q		30	0	30	0	30	120

**5.9.4 Expected Results for Test 5, 7 and 9**

INMME (17MHz Profiles): [462000... 741000]

INMME (30MHz Profiles): [924000...1483000]

## INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	240			0	0	0	0	0	0	0	0	0	0	0	0	0	0

## INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	30	0	30	0	30	0	30	120

**5.9.5 Expected results for Test 4, 6, 8 and 10**

INMME (17MHz Profiles): [462000... 741000]

INMME (30MHz Profiles): [924000...1483000]

## INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	240			0	0	0	0	0	0	0	0	0	0	0	0	0	0

## INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	0	30	0	30	0	30	0	150

**5.9.6 Expected Results for Test 11**

INMME (17MHz Profiles): [462000... 741000]

INMME (30MHz Profiles): [924000...1483000]

## INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	0	0	120			0	0	60			0	0	0	0	0	0	0

## INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	0	0	60	0	0	0	0	120

**5.9.7 Expected Results for Test 12**

INMME (17MHz Profiles): [462000... 741000]

INMME (30MHz Profiles): [924000...1483000]

## INMINPEQ Histogram

Bin	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Event Count	120			0	0	0	0	0	0	0	0	0	0	0	0	0	60

## INMIAT Histogram

Bin	0	1	2	3	4	5	6	7
Event Count	0	0	0	60	0	0	0	120

**5.9.8 PEIN Test Sequence Definition**

The PEIN test sequences, as defined in Annex A SHALL be used to generate the necessary number of impulses in order to perform the tests and populate the INMINPEQ and INMAIAT histograms.

The PEIN pulse SHALL be AWGN and have a bandwidth from 1MHz to 30MHz, with a pulse PSD of -90dBm/Hz.



### 5.10 Dying Gasp Test

Far-end Loss-of-Power (LPR-FE) failure is declared by the VTU-O after occurrence of a far-end LPR primitive (e.g. dying gasp message generated by VTU-R) followed by contiguous near-end LOS defects, detected by VTU-O (Section 7.1.1.2.3/G.997.1 [8]).

This test verifies that

- LPR-FE failure is generated after removal of power from the VTU-R
- the LPR-FE failure is not generated after successful initialization
- the LPR-FE failure is cleared when power to the VTU-R is restored and is followed by successful initialization
- the LPR-FE is not generated on loop disconnection only

**Table 49 – Dying Gasp Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration (use Figure 1).</li> <li>(2) According to the VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3).</li> <li>(3) Set the loop to             <ol style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ol> </li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Force a new initialization and wait for the modems to synchronize.</li> <li>(2) Wait for 1 minute after initialization.</li> <li>(3) Record the VTU-O LPR-FE failure bit state.</li> <li>(4) Disconnect the power supply from the VTU-R by removing the power supply from the mains supply.</li> <li>(5) Wait for 10 seconds.</li> <li>(6) Record the VTU-O LPR-FE failure state.</li> <li>(7) Re-apply power to the VTU-R by plugging in the power supply into the mains supply and wait for the modems to synchronize.</li> <li>(8) Wait for 1 minute after initialization.</li> <li>(9) Record the VTU-O LPR-FE failure state.</li> <li>(10) Disconnect the loop between the VTU-O and VTU-R.</li> <li>(11) Wait for 10 seconds.</li> <li>(12) Record the VTU-O LPR-FE failure state.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) No LPR-FE failure is present in MOP(3), MOP(9) and MOP(12).</li> <li>(2) LPR-FE failure is declared by the VTU-O in MOP(6).</li> </ol>

## 6 System Level Tests

### 6.1 64/65-Octet Encapsulation Far-End PTM-TC Performance Monitoring Test (Optional)

The purpose of this test is to verify that the access node and CPE use Clauses 30, 45 and 57/IEEE 802.3 for retrieval and reporting at the access node of the 64/65-Octet Encapsulation Far-End PTM-TC Performance Monitoring counters.

The PTM-TC functionality of VDSL2 implements 64/65-octet encapsulation as defined in Annex N/G.992.3 (see K.3.8/G.993.2 [6]).

However, the far end counters are not supported by the indicator bits or EOC messages specified in the G.992.x-series of ITU-T Recommendations or in G.993.2. They MAY be provided if the higher layer protocol running over this PTM-TC provides means (outside the scope of these Recommendations) to retrieve far end PTM-TC surveillance primitives from the far end, or through the proprietary OAM communication channel specified in clause 6 of G.997.1 (refer to the PTM data path far-end performance monitoring parameters in 7.2.5.2 /G.997.1).

If the PTM-TC carries Ethernet packets (802.3ah) [13], the Ethernet management function (residing above the  $\gamma$  reference point) maps the near end surveillance primitives and counters (obtained over the  $\gamma$  interface through access to clause 45 MDIO registers) into MIB objects defined in clause 30. MIB objects are exchanged with the far end using the Ethernet OAM PDU format and protocol defined in clause 57 (7.2.5.2 /G.997.1).

For the purpose of this optional system level test, the Access Node SHALL support the following minimum functionality related to IEEE 802.3 [12]:

- The AN SHALL operate in Active Mode (Clause 57.2.9).
- The AN SHALL support CPE operating in Passive Mode (Clause 57.2.9).
- The AN SHALL initiate OAM Discovery (Clause 57.3.2.1).
- The AN SHALL send and receive Information OAMPDUs (Clause 57.4.3.1).
- The AN SHALL send Variable Request OAMPDUs (Clause 57.4.3.3).
- The AN SHALL receive Variable Response OAMPDUs (Clause 57.3.2.1).
- The Clause 30 OAM counters SHALL be reported at the Q interface. The reporting format is out of the scope of this test, and MAY be one of the following examples:
  - i. Non-resettable counters (i.e., the format used in IETF EFMCu MIB [1]);
  - ii. Current/previous 15 minutes/1 day counters (i.e., the format used in ITU-T G.997.1).

The CPE SHALL support the following minimum functionality related to IEEE 802.3:

- The CPE SHALL operate in Passive Mode if the OAM Discovery process cannot be successfully completed with CPE in Active Mode (Clause 57.2.9).
- The CPE SHALL react to OAM Discovery process initiation (Clause 57.3.2.1).
- The CPE SHALL receive Variable Request OAMPDUs (Clause 57.4.3.3).
- The CPE SHALL send Variable Response OAMPDUs (Clause 57.4.3.4).
- The CPE SHALL support the TCCRCErrors and TCCodingViolations counters (Clause 30.11.2.1.9&10)
- The Clause 30 OAM counters (as contained in Variable Response OAMPDUs received from the CPE) SHALL be non-resettable counters (see 30.11.2.1.9&10), derived from the related Clause 45 MDIO registers (see Clause 45.2.6.11 and 45.2.6.12). The Clause 30 OAM counters SHALL be cleared to all zeros at system reset (as the Clause 45 registers) and SHALL not be cleared with a link state transition or when read

**Table 50 - 64/65-Octet Encapsulation Far-End PTM-TC Performance Monitoring Test (Optional)**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) Configure the SUT with specific line setting: FX_I_010_001 and the band-profile chosen for the test.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O with 0 length loop and no noise injected.</li> <li>(2) Force an initialization and wait for modem to sync. Wait 1 minute following synchronization.</li> <li>(3) Activate the CRC-PFE and CV-PFE performance monitoring counters on the access node.</li> <li>(4) Record the initial values of the CRC-PFE and CV-PFE performance monitoring counters at the access node.</li> <li>(5) Force a "micro-interruption" of 3ms (+ or – 0.5ms) every 10 seconds for 2.5min (for a total of 15 micro-interruptions).</li> <li>(6) Force performance monitoring counters update or wait for the counters to be updated at the access node.</li> <li>(7) Record the value of the CRC-PFE and CV-PFE performance monitoring counters at the access node.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) The VTU-R SHALL not lose sync with the VTU-O during the test.</li> <li>(2) The test result SHALL consist of reporting at the Q-interface (i.e. at the Access Node) the following two Clause 30 OAM counters: <ol style="list-style-type: none"> <li>a. CRC-PFE: Downstream TCCRCErrors counter (32-bit)</li> <li>b. CV-PFE: Downstream TCCodingViolations (32-bit)</li> </ol> </li> <li>(3) The Clause 30 OAM counters SHALL be observed before and after errors are induced on the loop. The test is passed if the downstream TCCodingViolations counter changes because of the errors induced. The downstream TCCRCErrors counter might or might not change, depending on the impact of the errors induced on the received 64/65-octet encapsulation syntax.</li> </ol>

NOTE - Further information on OAMPDU is provided in Appendix I.

## 7 Testing G.997.1 Configuration Parameters and Performance Monitoring Counters

These tests verify the G.997.1 [8] configuration parameters and performance monitoring counters.

### 7.1 Configuration Parameter MINSNRM

A test procedure for verification of the MINSNRM noise margin configuration parameter is shown in Table 51. The parameters MINSNRMds and MINSNRMus define the minimum noise margin the VTU-R/VTU-O receiver SHALL tolerate. This test procedure SHALL be applied to both the downstream and upstream directions.

**Table 51 - MINSNRM Control Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) According to the VDSL2 band-profile to be tested, configure the SUT in one of the profile line combinations associated to that band-profile in the rate adaptive mode (see Section 4.2.3). If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</li> <li>(3) SNRM test configurations: <ol style="list-style-type: none"> <li>a. MINSNRM = 5dB and TARSNRM=9dB</li> <li>b. MINSNRM = 8dB and TARSNRM=12dB</li> </ol> </li> <li>(4) Connect VTU-R and VTU-O through the 300m PE04 or 1kft 26AWG.</li> <li>(5) Additional test configurations: OPTIONAL OLR (SRA, SOS) SHALL NOT be used.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Inject -120dBm/Hz AWGN noise added at both the VTU-R and VTU-C ends. This power level is considered the 0dB noise power.</li> <li>(2) Let the modems train. Wait for 1 minute after initialization.</li> <li>(3) Increase the noise power level by 6dB.</li> <li>(4) Wait not more than 90 seconds for modem to retrain.</li> <li>(5) Repeat the test for each all SNRM test configurations.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) For all SNRM test configurations modems SHALL retrain.</li> </ol>

### 7.2 Configuration Parameter TARSNRM

A test procedure for verification of the TARSNRM noise margin configuration parameter is shown in Table 52. The parameters TARSNRMds and TARSNRMus define the noise margin the VTU-R/VTU-O receiver SHALL achieve to successfully complete initialization. This test procedure SHALL be applied to both the downstream and upstream directions.

**Table 52 - TARSNRM Control Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT in one of the profile line combinations associated to that band-profile in the rate adaptive mode (see Section 4.2.3).</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O through the second loop length defined for the chosen profile-line combination in the regional annex of TR-114.</li> </ol>

	<ul style="list-style-type: none"> <li>(2) Inject the TR-114 crosstalk noise applicable for that testloop at both the VTU-R and VTU-O ends.</li> <li>(3) Let the modems train. Wait for 1 minute after initialization.</li> <li>(4) Record the reported SNR margin, SNRMds and SNRMus.</li> <li>(5) Repeat the test 3 times.</li> </ul>
<b>Expected Result</b>	<ul style="list-style-type: none"> <li>(1) For Annex A: Each reported SNR margin SHALL be <math>\geq</math> (TARSNRM – 2 dB).</li> <li>(2) For Annex B: Each reported SNR margin SHALL be <math>\geq</math> (TARSNRM – 1 dB).</li> </ul>

### 7.3 Configuration Parameter PSDMASK

A test procedure for verification of the PSDMASK configuration parameter is shown in Table 53. The parameters PSDMASKds and PSDMASKus define the MIB PSD mask MIBMASK and it MAY impose additional PSD restrictions for the passbands compared to the Limit PSD mask specified in the regional annexes of G.993.2.

**Table 53 - PSDMASK Control Test**

<b>Test Configuration</b>	<ul style="list-style-type: none"> <li>(1) SeeSection 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT with one of the profile line combinations associated to that band-profile (see section 4.2.3).</li> <li>(3) Additional test conditions: <ul style="list-style-type: none"> <li>a. Set the PSDMASK for passbands only and restrict the transmit PSD to levels below those allowed by the applicable Limit PSD mask.</li> </ul> </li> </ul>
<b>Method of Procedure</b>	<ul style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O through the shortest loop length defined for the chosen profile-line combination in the regional annex of TR-114 [2].</li> <li>(2) Wait 1 minute following synchronization.</li> <li>(3) Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the PSD to be measured. If it does not see the NOTE in Table 40.</li> <li>(4) The PSD SHALL be measured in one of the following ways: <ul style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyzer)</li> </ul> </li> </ul> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the power measurement.</p>
<b>Expected Result</b>	<ul style="list-style-type: none"> <li>(1) Measured PSD SHALL NOT exceed the MIB PSD mask (MIBMASK) and Limit PSD mask (LMITMASK).</li> <li>(2) Measured PSD SHALL comply with the requirements from Section 7.2.3/G.993.2. [6].</li> </ul>

#### 7.4 Configuration Parameter VDSL2-CARMASK

A test procedure for verification of the VDSL2-CARMASK configuration parameter is shown in Table 54. This parameter defines the restrictions, additional to the band plan, to determine the set of subcarriers allowed for transmission. Test procedure SHALL be applied to both the downstream and upstream directions.

**Table 54 - VDSL2 CARMASK Control Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 the band-profile to be tested, configure the SUT in one of the profile-line combinations associated to that band-profile (see Section 4.2.3).</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Configure VTU-R and VTU-O with target SNR margin set to 6dB. Set VDSL2-CARMASK to one that is associated with the used profile line combination.</li> <li>(2) Connect VTU-O and VTU-R through the shortest loop length defined for the chosen profile-line combination in the regional annex of TR-114.</li> <li>(3) Let the modems train. Wait for 1 minute after initialization.</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) The reported bits of disabled subcarriers BITSpsds and BITSpsus SHALL be set to 0.</li> </ol>

#### 7.5 Configuration Parameter MAXNOMATP

A test procedure for verification of the MAXNOMATP configuration parameter is shown in Table 55. This test procedure SHALL be applied to both the downstream and upstream directions.

**Table 55 - MAXNOMATP Control Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT in one of the profile-line combinations associated to that band-profile (see section 4.2.3).</li> <li>(3) Additional test conditions for downstream test: <ol style="list-style-type: none"> <li>a. MAXNOMATPds = 6.7dBm</li> <li>b. MAXNOMATPds = 0dBm</li> </ol> NOTE - MAXNOMATPus=14.5dBm (Table 6-1/G.993.2).</li> <li>(4) Additional test conditions for upstream test (optional): <ol style="list-style-type: none"> <li>a. MAXNOMATPus = 3.3dBm</li> <li>b. MAXNOMATPus = 0dBm</li> </ol> NOTE - MAXNOMATPds is defined in Table 1.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Connect VTU-O and VTU-R through the shortest loop length defined for the chosen profile-line combination in the regional annex of TR-114 [2].</li> <li>(2) Wait 1 minute following synchronization.</li> <li>(3) Record the reported values of ACTATPds and ACTATPus</li> <li>(4) Disconnect the line. The VDSL2 link SHOULD stay in L0 long enough for the power to be measured (NOTE).</li> <li>(5) The power generated SHALL be measured in one of the following ways: <ol style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the</li> </ol> </li> </ol>

	<p>VTU termination impedance) and a high-impedance differential probe</p> <p>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyzer)</p> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an effect of <math>\leq 0.5\text{dB}</math> on the power measurement.</p> <p>(6) Repeat the test for each MAXNOMATPds from TC(3).</p> <p>(7) Repeat the test for each MAXNOMATPus from TC(4)</p>
<b>Expected Result</b>	<p>(1) For each test the reported actual power SHALL be <math>\leq</math> the configured MAXNOMATP.</p> <p>(2) For each test the measured power SHALL be <math>\leq</math> the configured MAXNOMATP.</p>
<p>NOTE - If the VTUs cannot operate in the mode described in MOP(4), the test setup SHALL provide adequate isolation of the downstream and upstream transmit signals between the two transceivers to allow for an accurate measurement to be made, while both transceivers remain connected and in state L0. If mode described in MOP(4) is unavailable, the measurements will not be made on loops or attenuation settings not providing adequate isolation, and the measurement method used will be noted within the test report.</p>	

## 7.6 Performance Monitoring Counters for Code Violations and Errored Seconds

Test procedures for verification of the channel performance monitoring parameter CV and line performance monitoring parameter ES in the fast and interleaved modes are shown in Table 56 and Table 57, respectively.

**Table 56 - Code Violation and Errored Seconds Test in the Fast Mode**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT in FX_F_003_001 specific line-setting.</p> <p>(3) Additional test conditions: optional OLR (SRA, SOS) SHALL NOT be used.</p>
---------------------------	--

<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O with 0 length loop and no noise injected.</li> <li>(2) Wait 1 minute following synchronization.</li> <li>(3) Note down the initial value of the CV-C, CV-CFE, ES-L, ES-LFE, SES-L, SES-LFE, UAS-L and UAS-LFE performance monitoring counters at the VTU-O.</li> <li>(4) Note down the initial value of the CV-C, ES-L, SES-L and UAS-L at the VTU-R.</li> <li>(5) Force a "micro-interruption" of 3ms (+ or – 0.5ms) every 10 seconds for 2.5min (for a total of 15 micro-interruptions).</li> <li>(6) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</li> <li>(7) Note down the value of the counter CV-C, ES-L, SES-L and UAS-L at the VTU-R.</li> <li>(8) Note down the value of the counters CV-C and CV-CFE, ES-L and ES-LFE, SES-L and SES-LFE, and UAS-L and UAS-LFE at the VTU-O.</li> <li>(9) Calculate the increase of these counters between MOP(7) and MOP(4).</li> <li>(10) Calculate the increase of these counters between MOP(8) and MOP(3).</li> </ol>
<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) No loss of synchronization SHALL occur during the test.</li> <li>(2) At the VTU-O. no increase of SES-L, SES-LFE, UAS-L and UAS-LFE SHALL be reported.</li> <li>(3) At the VTU-O, the increase of the ES-L, ES-LFE, CV-C and CV-CFE counters SHALL be <math>\geq 15</math> and <math>\leq 35</math> for DS and <math>\leq 32</math> for US.</li> <li>(4) At the VTU-R. no increase of SES-L and UAS-L, if available, SHALL be reported.</li> <li>(5) At the VTU-R, the increase of CV-C and ES-L counters SHALL be at least equal to 15 and <math>\leq 35</math> for DS and <math>\leq 32</math> for US.</li> <li>(6) The increase of CV-C counter at the VTU-R SHALL be equal to the increase of CV-CFE counter at the VTU-O.</li> <li>(7) The increase of ES-L counter at the VTU-R SHALL be equal to the increase of ES-LFE counter at the VTU-O.</li> </ol>

NOTE1: The numbers in step ER(3) and ER(5) are computed taking into account up to 5 CRC in DS and 2 CRC in US due to  $10^{-7}$  BER in the fast mode, in 3 minutes test duration.

NOTE2: If the duration of the overhead frame is shorter than  $\frac{1}{2}$  of the micro-interruption length the increase of CV-C counter at the VTU-R, as well as the increase of both CV-CFE and CV-C counters at the VTU-O, SHALL be  $\geq 15$  and  $\leq 50$  for DS and  $\leq 47$  for US.



**Table 57 - Code Violation and Errored Seconds Test in the Interleaved Mode**

<b>Test Configuration</b>	<ul style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT according to Section 4.2 in FX_I_010_001 specific line-setting defined in Table 12.</li> <li>(3) Additional test conditions: optional OLR (SRA, SOS) SHALL NOT be used.</li> </ul>
<b>Method of Procedure</b>	<ul style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O with 0 length loop and no noise injected.</li> <li>(2) Wait 1 minute following synchronization.</li> <li>(3) Report the actual impulse noise protection in US (ACTINPus) and DS (ACTINPds).</li> <li>(4) Calculate the micro-interruption duration as:  <math display="block">[(\max(\text{ACTINPus}, \text{ACTINPds}) + 1) \times 0.25\text{ms}] \times 2</math> and rounded up to the nearest ms.</li> <li>(5) Note down the initial value of the CV-C, CV-CFE, ES-L, ES-LFE, SES-L, SES-LFE, UAS-L and UAS-LFE performance monitoring counters at the VTU-O.</li> <li>(6) Note down the initial value the CV-C, ES-L, SES-L and UAS-L at the VTU-R.</li> <li>(7) Force one micro-interruption of the duration calculated in MOP(4) every 10 seconds for 2.5min (for a total of 15 micro-interruptions).</li> <li>(8) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</li> <li>(9) Note down the value of the counter CV-C, ES-L, SES-L and UAS-L at the VTU-R.</li> <li>(10) Note down the value of the counters CV-C and CV-CFE, ES-L and ES-LFE, SES-L and SES-LFE, and UAS-L and UAS-LFE at the VTU-O.</li> <li>(11) Calculate the increase of these counters between MOP(9) and MOP(6).</li> <li>(12) Calculate the increase of these counters between MOP(10) and MOP(5).</li> </ul>
<b>Expected Result</b>	<ul style="list-style-type: none"> <li>(1) No loss of synchronization SHALL occur during the test.</li> <li>(2) At the VTU-O no increase of SES-L, SES-LFE, UAS-L and UAS-LFE SHALL be reported.</li> <li>(3) At the VTU-O, the increase of the ES-L, ES-LFE, CV-C and CV-CFE counters SHALL be <math>\geq 15</math> and <math>\leq 35</math> for DS and <math>\leq 31</math> for US.</li> <li>(4) At the VTU-R no increase of SES-L and UAS-L, if available, SHALL be reported.</li> <li>(5) At the VTU-R, the increase of CV-C and ES-L counters SHALL be <math>\geq 15</math> and <math>\leq 35</math> for DS and <math>\leq 31</math> for US.</li> <li>(6) The increase of CV-C counter at the VTU-R SHALL be equal to the increase of CV-CFE counter at the VTU-O.</li> <li>(7) The increase of ES-L counter at the VTU-R SHALL be equal to the increase of ES-LFE counter at the VTU-O.</li> </ul>

NOTE1: The numbers in step ER(3) and ER(5) are computed taking into account up to 5 CRC in DS and 1 CRC in US due to  $10^{-7}$  BER in the interleaved mode, in 3 minutes test duration.

NOTE2: If the duration of the overhead frame is shorter than  $\frac{1}{2}$  of the micro-interruption length the increase of CV-C counter at the VTU-R, as well as the increase of both CV-CFE and CV-C counters at the VTU-O, SHALL be  $\geq 15$  and  $\leq 50$  for DS and  $\leq 46$  for US.

## 7.7 Performance Monitoring Counter for SES

A test procedure for verification of the line performance monitoring parameter SES is shown in Table 58.

**Table 58 - SES Counter Reporting Test**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT in RA_F_150_150, RA_I_150_150 or RA_R-17/2/41_150_150 specific line-setting (see Section 4.2.3).</li> <li>(3) Additional test conditions: OPTIONAL OLR (SRA, SOS) SHALL NOT be used.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O through 1350 feet 26AWG or 450 m PE04.</li> <li>(2) Set the noise generator to -120dBm/Hz AWGN at the VTU-R and at the VTU-O side of the loop.</li> <li>(3) Force an initialization and wait for modem to sync. Wait 1 minute following synchronization.</li> <li>(4) Note down the initial value of the SES-L, SES-LFE, UAS-L and UAS-LFE performance monitoring counters at the VTU-O and the initial value of the SES-L and UAS-L counters at the VTU-R.</li> <li>(5) Inject the noise impulse, -110dBm/Hz AWGN at the VTU-R side of the loop, with duration of <math>590 \pm 10</math> milliseconds for RA_F_150_150 and RA_I_150_150, and with duration of <math>630 \pm 10</math> ms for RA_R-17/2/41_150_150.</li> <li>(6) Repeat MOP(5) 14 times (for a total of 15 impulse events) with 10s between each event.</li> <li>(7) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</li> <li>(8) Note down the value of the counter SES-L and UAS-L at the VTU-R. Note down the value of the counters SES-L and SES-LFE, and UAS-L and UAS-LFE at the VTU-O.</li> <li>(9) Calculate the increase of these counters between MOP(8) and MOP(4).</li> <li>(10) Repeat MOP(5) to MOP(9), but inject the noise impulse at the VTU-O side of the loop.</li> </ol>

<b>Expected Result</b>	<ul style="list-style-type: none"> <li>(1) No loss of synchronization SHALL occur during the test.</li> <li>(2) No increase of UAS-L and UAS-LFE at the VTU-O SHALL be reported during the test time.</li> <li>(3) If available, no increase of UAS-L at the VTU-R SHALL be reported.</li> <li>(4) The increase of SES-L counter at the VTU-R SHALL be equal to the increase of SES-LFE counter at the VTU-O.</li> <li>(5) For injecting the impulse noise at the VTU-R, the increase of SES-L counter at the VTU-R and SES-LFE counter at the VTU-O, SHALL be at least equal to 15 and <math>\leq 30</math>.</li> <li>(6) For injecting the impulse noise at the VTU-O, the increase of SES-L counter at the VTU-O SHALL be <math>\geq 15</math> and <math>\leq 30</math>.</li> </ul>
------------------------	--

### 7.8 Performance Monitoring Counter for Unavailable Seconds (UAS)

A test procedure for verification of the line performance monitoring parameter UAS is shown in Table 59.

**Table 59 - Unavailable Seconds (UAS) Reporting Test**

<b>Test Configuration</b>	<ul style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT according to section 4.2 in FX_I_010_001 specific line-setting defined in Table 12.</li> <li>(3) Additional test conditions: OPTIONAL OLR (SRA, SOS) SHALL NOT be used.</li> </ul>
<b>Method of Procedure</b>	<ul style="list-style-type: none"> <li>(1) Connect VTU-R and VTU-O with 0 length loop and no noise injected.</li> <li>(2) Wait 1 minute following synchronization.</li> <li>(3) Note down the initial value of the UAS-L and UAS-LFE performance monitoring counters at the VTU-O and the initial value of the UAS-L counter at the VTU-R.</li> <li>(4) Disconnect the line, and wait for modem to transit from L0 to L3 state. Wait at least 1 minute before reconnecting the line and wait for the transition back to L0 state.</li> <li>(5) Measure the duration between the line disconnection and the moment that the operational state of the line at the VTU-O is reported as 'in Showtime'.</li> <li>(6) Force performance monitoring counters update and wait for 30 seconds for the counters to be read out.</li> <li>(7) Note down the value of these counters (UAS-L and UAS-LFE) on the VTU-O and the value of the UAS-L counter at the VTU-R.</li> <li>(8) Calculate the increase of the UAS counters between MOP(7) and MOP(3).</li> </ul>

<b>Expected Result</b>	<ol style="list-style-type: none"> <li>(1) The modem SHALL drop the connection after the disconnection of the line.</li> <li>(2) <math>\Delta</math> UAS-L calculated at the VTU-O SHALL not differ from the value measured in MOP(5) by more than 10s.</li> <li>(3) If available, the <math>\Delta</math> UAS-L calculated at the VTU-R SHALL not differ from the value measured in MOP(5) by more than 10s.</li> <li>(4) <math>\Delta</math> UAS-LFE calculated at the VTU-O SHALL not differ from the value measured in MOP(5) by more than 14s.</li> <li>(5) If available, <math>\Delta</math> UAS-L calculated at the VTU-R SHALL SHALL not differ from the value of <math>\Delta</math> UAS-LFE calculated at the VTU-O by more than 13s.</li> </ol>
------------------------	--

## 7.9 Performance Monitoring Counters for Full initialization and Failed Full initialization

A test procedure for verification of the full initialization and failed full initialization performance monitoring parameter is shown in Table 60.

**Table 60 - Full Initialization Count and Failed Full Initialization Count Test**


<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT according to Section 4.2 in FX_I_040_006 specific line-setting defined in Table 12.</li> <li>(3) Additional test conditions: optional OLR (SRA, SOS) SHALL not be used.</li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Record the initial values of the Full initialization count and the Failed full initialization count at the VTU-O.</li> <li>(2) Connect VTU-R and VTU-O with 0 length loop and no noise injected.</li> <li>(3) Wait 1 minute following synchronization.</li> <li>(4) Disconnect the line for at least 7 seconds.</li> <li>(5) Wait for the modem to retrain.</li> <li>(6) Wait for 1 minute following synchronization.</li> <li>(7) Record the value of Full initialization count and Failed full initialization count reported by VTU-O.</li> <li>(8) Reconnect the line but with 1050m PE04 or 3.5kft 26AWG loop.</li> <li>(9) Wait for 90s.</li> <li>(10) Record the value of Full initialization count and Failed full initialization count reported by VTU-O.</li> <li>(11) Repeat MOP(1) to MOP(10) four times.</li> </ol>

<p><b>Expected Result</b></p>	<p>For each of the 5 test repetitions:</p> <ol style="list-style-type: none"> <li>(1) The increase of the Full initialization count calculated as the difference between the values from MOP(7) and MOP(1) SHALL be <math>\geq 2</math>.</li> <li>(2) Calculated as the difference between the values from MOP(7) and MOP(1), the increase of the Full initialization count minus the increase of the Failed full initialization count SHALL be = 2.</li> <li>(3) The increase of the Failed full initialization count calculated as the difference between the values from MOP(10) and MOP(7) SHALL be <math>\geq 1</math>.</li> <li>(4) Calculated as the difference between the values from MOP(10) and MOP(7), the increase of the Full initialization count SHALL be equal to the increase of the Failed full initialization count.</li> </ol>
-------------------------------	---

**7.10 Inhibition of Performance Monitoring Counters**

Purpose of these tests is to verify that the inhibition and non-inhibition of some DSL performance counters (CV, ES, SES, LOSS) is implemented correctly according to Section 7.2.7.13/G.997.1 [8].

The test SHALL be done with bursts of the repetitive impulse noise (REIN) in addition to the background noise. The REIN noise duration is  $T_{Burst}$ . The REIN pulse consists of a “Burst of pseudo random AGN” at a level of  $-90\text{dBm/Hz}$  differential mode from 25 kHz up to 30 MHz, where the out-of-band noise shall not be higher than  $-140\text{dBm/Hz}$ . The pulse duration  $\Delta_{REIN}$  depends on the specific test profile. The pulse SHALL be repeated every 10 ms ( $T_{REIN}$ ).



**Figure 5 - REIN Noise for the inhibition test of CV, ES, SES and LOSS counter**

**Table 61 - Test of inhibition and non-inhibition of CV, ES, SES, LOSS counters**

<b>Test Configuration</b>	<ol style="list-style-type: none"> <li>(1) See Section 4.1 for the test configuration.</li> <li>(2) As per VDSL2 band-profile to be tested, configure the SUT according to the Specific Line Setting “RA_F_150_150” and “RA_I_150_150”, as defined in Section 4.2.2.</li> <li>(3) Additional test conditions: OPTIONAL OLR (SRA, SOS) SHALL not be used.</li> <li>(4) Connect VTU-O and VTU-R to             <ol style="list-style-type: none"> <li>a. 1350ft 26AWG for profiles up to 17MHz or 450ft 26AWG for 30MHz profiles</li> <li>or</li> <li>b. 450m PE 0.4mm for profiles up to 17MHz or 150m PE 0.4mm for 30MHz profiles</li> </ol> </li> </ol>
<b>Method of Procedure</b>	<ol style="list-style-type: none"> <li>(1) Set the noise generator to -120dBm/Hz AWGN at the VTU-R side and to -110dBm/Hz AWGN at the VTU-O side of the loop.</li> <li>(2) Force an initialization and wait for modem to sync. Wait 1 minute following synchronization.</li> <li>(3) Note down the value of the CV-C, CV-CFE, ES-L, ES-LFE, SES-L, SES-LFE, LOSS-L and LOSS-LFE performance monitoring counters at the VTU-O and, if available, the value of the CV-C, ES-L, SES-L and LOSS-L counters at the VTU-R.</li> <li>(4) Inject the REIN noise of duration <math>T_{Burst}=2sec</math> at the VTU-R side of the loop with a pulse duration <math>\Delta_{REIN}</math> depending on the specific test profile:             <ul style="list-style-type: none"> <li>• RA_F_150_150: <math>\Delta_{REIN} = 100\mu s</math></li> <li>• RA_I_150_150: calculate <math>\Delta_{REIN}</math> as                 <ol style="list-style-type: none"> <li>a. <math>[(\max(\text{ACTINP}_{us}, \text{ACTINP}_{ds}) + 1) \times 0.25ms] \times 2</math>, rounded up to the nearest ms, for profiles up to 17MHz</li> <li>b. <math>[(\max(\text{ACTINP}_{us}, \text{ACTINP}_{ds}) + 1) \times 0.125ms] \times 2</math>, rounded up to the nearest ms, for the 30MHz profiles</li> </ol> </li> </ul> </li> <li>(5) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</li> <li>(6) Note down the values of the counters as in MOP(3).</li> <li>(7) Calculate the increase of these counters between the values from MOP(6) and MOP(3).</li> <li>(8) Force one "micro-interruption" of duration 200ms.</li> <li>(9) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</li> <li>(10) Note down the values of the counters as in MOP(3).</li> <li>(11) Calculate the increase of these counters between the values from MOP (10) and MOP (6).</li> <li>(12) Inject the REIN noise as in MOP(4) but with <math>T_{Burst} = 15sec</math>.</li> <li>(13) If the modems retrain, wait until they reach showtime.</li> <li>(14) Wait 10 seconds.</li> <li>(15) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</li> <li>(16) Note down the values of the counters as in MOP(3).</li> <li>(17) Calculate the increase of these counters between the values from MOP(16) and MOP(10).</li> </ol>

<p><b>Expected Result</b></p>	<p><b>At The VTU-R (if available):</b></p> <p>(1) As measured in MOP(7), the increase of SES-L counter SHALL be <math>\geq 2</math> and <math>\leq 3</math>.  If the increase of SES-L counter is 3, the increase of CV-C counter SHALL be <math>\leq 1</math>.  If the increase of SES-L counter is 2, the increase of the CV-C counter SHALL be <math>&lt; 18 \times 32 + 1</math>.</p> <p>(2) As measured in MOP(7), the increase of the ES-L counter SHALL be <math>\geq 2</math> and <math>\leq 4</math>.</p> <p>(3) As measured in MOP(11), the increase of the LOSS-L counter SHALL be <math>\geq 1</math> and <math>\leq 2</math>.</p> <p>(4) As measured in MOP(17), the increase of the ES-L counter SHALL be <math>\leq 2</math>.</p> <p>(5) As measured in MOP(17), no increase of the SES-L and LOSS-L counters SHALL be reported.</p> <p><b>At the VTU-O:</b></p> <p>(6) As measured in MOP(7), the increase of SES-LFE counter SHALL be <math>\geq 2</math> and <math>\leq 3</math>.  If the increase of SES-LFE counter is 3, the increase of CV-CFE counter SHALL be <math>\leq 1</math>.  If the increase of SES-LFE counter is 2, the increase of the CV-CFE counter SHALL be <math>&lt; 18 \times 32 + 1</math>.</p> <p>(7) As measured in MOP(7), the increase of the ES-LFE counter SHALL be <math>\geq 2</math> and <math>\leq 4</math>.</p> <p>(8) As measured in MOP(11), the increase of the LOSS-LFE counter SHALL be <math>\geq 1</math> and <math>\leq 2</math>.</p> <p>(9) As measured in MOP(17), the increase of the ES-LFE counter SHALL be <math>\leq 2</math>.</p> <p>(10) As measured in MOP(17), no increase of the SES-LFE and LOSS-LFE counters SHALL be reported.</p>
-------------------------------	---

## **Annex A PEIN Test Sequences**

PEIN Test Sequences are contained in the file *TR-115\_Issue-3.xls*.



## Appendix I Additional Information about OAM Protocol Data Unit (OAMPDU) (informative)

The Information OAMPDU at the end of the Discovery process is shown in Table 62 for both downstream (-O side transmit) and upstream (-R side transmit). In this example, the capabilities reflect the minimum functionality required in Section 6.1. However, other capabilities that are not essential to perform this test might also be indicated.

The Variable Request and Variable Response OAMPDUs to retrieve both counters are shown in Table 63 through Table 66, These examples show the basic single request/response OAMPDUs. However, a Variable Request OAMPDU MAY contain multiple Variable Descriptors, and a Variable Response OAMPDU MAY contain multiple Variable Containers, in order to retrieve multiple counter values at once.

**Table 62 - Example Information OAMPDU after OAM discovery**

	Octets	Downstream	Upstream
<b>Header</b>			
MAC destination @	6	0x0180C2000002	0x0180C2000002
MAC source @	6	MAC source @	MAC source @
Length/Type	2	0x8809	0x8809
Subtype	1	0x03	0x03
FLAGS	2	0x0050	0x0050
CODE	1	0x00	0x00
<b>Local TLV</b>			
Information Type	1	0x01	0x01
Information Length	1	0x10	0x10
OAM version	1	0x01	0x01
Revision	2	Counter-O	Counter-R
State	1	0x00	0x00
OAM configuration	1	0x01	0x10
OAMPDU	2	MAXPDUsize-O	MaxOAMPDUsize-R
OUI Vendor ID	3	IEEEvendorID-O	IEEEvendorID-R
Vendor specific	4	VendorSpecific-O	VendorSpecific-R
<b>Remote TLV</b>			
Information Type	1	0x02	0x02
Information Lenth	1	0x10	0x10
OAM version	1	0x01	0x01
Revision	2	Counter-R	Counter-O
State	1	0x00	0x00
OAM configuration	1	0x10	0x01
OAMPDU	2	MaxOAMPDUsize-R	MaxOAMPDUsize-O
OUI Vendor ID	3	IEEEvendorID-R	IEEEvendorID-O
Vendor specific	4	VendorSpecific-R	VendorSpecific-O
<b>PAD</b>	10	All 0x00	All 0x00
<b>FCS</b>	4	FCS	FCS

**Table 63 - Variable Request OAMPDU to retrieve TCCRCErrors Counter**

	Octets	Value
<b>Header</b>		
MAC destination @	6	0x0180C2000002
MAC source @	6	MAC source @
Length/Type	2	0x8809
Subtype	1	0x03
FLAGS	2	0x0050
CODE	1	0x02
<b>Variable Descriptor for TCCRCErrors</b>		
Branch	1	0x07
Leaf	2	0x014C
<b>PAD</b>	39	All 0x00
<b>FCS</b>	4	FCS

**Table 64 - Variable Response OAMPDU to retrieve TCCRCErrors Counter**

	Octets	Value
<b>Header</b>		
MAC destination @	6	0x0180C2000002
MAC source @	6	MAC source @
Length/Type	2	0x8809
Subtype	1	0x03
FLAGS	2	0x0050
CODE	1	0x03
<b>Variable Container for TCCRCErrors</b>		
Branch	1	0x07
Leaf	2	0x014C
Width	1	0x04
Value	4	counter
<b>PAD</b>	34	All 0x00
<b>FCS</b>	4	FCS

**Table 65 - Variable Request OAMPDU to retrieve TCCodingViolations Counter**

	Octets	Value
<b>Header</b>		
MAC destination @	6	0x0180C2000002
MAC source @	6	MAC source @
Length/Type	2	0x8809
Subtype	1	0x03
FLAGS	2	0x0050
CODE	1	0x02
<b>Variable Descriptor for TCCodingViolations</b>		
Branch	1	0x07
Leaf	2	0x0160
<b>PAD</b>	39	All 0x00
<b>FCS</b>	4	FCS

**Table 66 - Variable Response OAMPDU to retrieve TCCodingViolations counter**

	Octets	Value
<b>Header</b>		
MAC destination @	6	0x0180C2000002
MAC source @	6	MAC source @
Length/Type	2	0x8809
Subtype	1	0x03
FLAGS	2	0x0050
CODE	1	0x03
<b>Variable Container for TCCodingViolations</b>		
Branch	1	0x07
Leaf	2	0x0160
Width	1	0x04
Value	4	counter
<b>PAD</b>	34	All 0x00
<b>FCS</b>	4	FCS

End of Broadband Forum Technical Report TR-115